

MEMORANDUM

DATE: April 24, 2024

TO: Responsive Bidders on SUB-BASE PREP, HAUL AND PLACE HOT MIX ASPHALT

FROM: Eric Imes
Public Works Director
Morrow County

RE: Addendum 1 to ITB SUB-BASE PREP, HAUL AND PLACE HOT MIX ASPHALT

The enclosed Addendum has been made to ITB SUB-BASE PREP, HAUL AND PLACE HOT MIX ASPHALT

If there are any questions, please contact me at:

Email: eimes@co.morrow.or.us

ADDENDUM 1 INVITATION TO BID – SUB-BASE PREP, HAUL AND PLACE HOT MIX ASPHALT

The following include the necessary changes. Please refer to the following sections.

IP-1 Time and Place for Receiving Bids

- A. Bids for the herein described materials and services will be received by Morrow County Public Works on or before Thursday April 25, 2024, 2:00 p.m., P.S.T. at the Morrow County Public Works office 365 West Highway 74 Lexington, OR. 97839 in person or via UPS or Fed-Ex.
- B. Hand delivered or mailed bids must be in a sealed envelope marked "Paving ITB".
- C. Bids will be opened Thursday April 25, 2024, 2:00 p.m., P.S.T. at the Morrow County Public Works Office, 365 West Highway 74 Lexington, Oregon.
- D. A pre-bid conference is mandatory. Bids from Contractors not in attendance will be considered non-responsive. The pre-bid meeting will be held Wednesday April 24, 2024, at 1:00 pm in Boardman Oregon at the corner of Rippee Rd. and Root Ln.
- E. Bids may be delivered by email to eimes@co.morrow.or.us. Email shall be delivered between 2:00 and 2:05 pm. Bids delivered by email will be opened in witness of the bid selection panel to ensure the integrity of the sealed competitive bidding process.

IP-2 Scope of Work and Materials

- A. Contractor shall haul and place Hot Mix Asphalt for Morrow County Public Works on Toms Camp between Kunze and the canal, and Root Ln between Wilson and Rippee. Paved surface shall be a 1" compacted average pre-level and a 2" compacted overlay. Paved width shall be 21'. Root Ln is estimated at 5200 linear feet. Toms Camp is estimated at 2755 linear feet.
- B. Contractor shall use Hot Mix Asphalt as described below.
 - a. ½" ACP Level 3 Hot Mix
 - b. ½" ACP Level 3 Hot Mix shall meet Oregon Department of Transportation (ODOT) Specifications, section 00744
- C. Morrow County estimates quantities of Hot Mix Asphalt at 3,300 tons.
- D. Contractor will provide traffic control as described in the Oregon temporary traffic control handbook.
- E. Morrow County will prepare all shoulders for paving.
- F. Contractor to supply and apply approved tack coat at a rate of .10 PSY.
- G. Contractor will supply and place Temporary Pavement Markers at centerline following paving of the second lift at a span of 50 feet.
- H. Morrow County will place shoulder rock following completion of the paving phase.
- I. Morrow County will supply and apply permanent pavement markings and striping.

IP-4 Bid Schedule

Item No.	Description	Unit	Quantity	Unit Price	Total Cost
1.	Mobilization	lump sum	1	\$	\$
2.	Sub base phase	lump sum	1	\$	\$do not bid
3.	½" 64-22 ACP Level 3	placed tons	3300	\$	\$
4.	Pavement markers	lump sum	1	\$	\$
5.	Traffic control	lump sum	1	\$	\$

TOTAL BID PRICE \$

Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid items will be based on actual quantities, determined as provided. Placing hot mix above and beyond 3,300 tons must be approved via email by the public works director eimes@co.morrow.or.us. Any hot mix, labor, or equipment used to pave above or beyond 3,300 tons without prior approval will not be paid.

By: _____

Company Name: _____

Print Name: _____

Mailing Address: _____

Title: _____

Phone: _____

Oregon CCB #: _____

