


R-3

CORNER RESTORATION


CORNER: 1/4 corner common to Sections 19 and 30, T1N, R23E, W.M.
ORIGINAL SURVEY BY: David P. Thompson
CONTRACT NUMBER: 119
CONTRACT DATE: February 15, 1867



ORIGINAL DESCRIPTION: Set stone 16x10x6. No bearing objects.

RESTORATION BY, STAMP, AND DATE:

Benjamin B. Beseda, PLS 50800
 Field Work completed January 13, 2012
 Field Crew Bradley R. Huffmon, PLS 2786, Crew Chief
 And Rob Walker, Survey Tech.



EVIDENCE FOUND: found stone fitting original description. Ancient east-west fence is approx. 1.5' north of stone. Ancient fence posts line up with stone to the south.

DESCRIPTION OF MONUMENTS AND ACCESSORIES SET AND METHODS USED:

Found stone in good condition.

5/8"x.30" rebar with yellow plastic cap stamped "B BESEDA PLS 50800" flush with the ground bear as references as follows from the 1/4 corner:

- 1) North 33° 55' 40" East 68.42'
- 2) South 45° 07' 10" East 68.50'
- 3) South 33° 00' 23" West 50.89'
- 4) North 28° 42' 09" West 57.61'