

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION $\frac{4}{9} \frac{3}{10}$ TIN. R26E. W.M.	TOWNSHIP T I N	RANGE R 26 E OF THE WILLAMETTE MERIDIAN	DATE AUGUST 2008
MORROW COUNTY		(Please check one)	
CORNER DESIGNATION:		<input type="checkbox"/> Condition Report Only <input checked="" type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input checked="" type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out	
$\frac{4}{9} \frac{3}{10}$ TIN. R26E. W.M. MORROW COUNTY. OREGON Previous Renewals / Surveys. etc. ORIGINAL GLO SURVEY BY E. HAFT IN 1861.			
Monument(s) & Accessories Found: (Condition & Source) LOCATED IN CUT FOR GRIEB LANE A COUNTY ROAD. AN OLD FENCE LINE WITH ITS PLOW LINE RUNS NORTH.			
Monument Detail: <div style="text-align: center; border: 1px solid black; border-radius: 50%; width: 100px; height: 100px; margin: 0 auto; display: flex; flex-direction: column; align-items: center; justify-content: center;"> TIN R 26 E <hr style="width: 50%;"/> 413 9110 2008 LS 2850 </div>	Sketch: 		
Monument Set (Procedures and Description): MONUMENT SET AT INTERSECTION OF OLD FENCE AND CENTER OF GRIEB LANE. SEE MORROW COUNTY PARTITION PLAT 2008-2 DONE BY ME FOR DETAILS.			
New Accessories: 5/8" X 30" STEEL REBAR WITH PLASTIC CAP STAMPED LS 2850 BEARS WEST 20.03'. 2 3/8" BRASS CAP WITNESS CORNER ON A 2" X 30 PIPE BEARS NORTH 19.84'. "T" POST WITH A WARNING POSTER AND A BEARING OBJECT SIGN BEARS NORTH 20.13'. A 1" STEEL SHAFT INSIDE OF A GALVANIZED PIPE BEARS EAST 19.48'. NOTE: MONUMENTS AND REFERENCES LOCATED WITHIN GRIEB LANE ARE 0.2' BELOW SURFACE.			
Location & Comments:		Compass Declination:	
LOCATED AT CENTER OF GRIEB LANE.		NOT DETERMINED	
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPPNER. OR 97836			
Party Chief JUDSON L. COPPOCK LS 2850			
Notes		<div style="border: 1px solid black; padding: 5px; text-align: center;"> SURVEYOR'S SEAL REGISTERED PROFESSIONAL LAND SURVEYOR </div>	
Witness		<div style="display: flex; align-items: center; justify-content: center;"> <div style="margin-left: 10px;"> OREGON JANUARY 20 1998 JUDSON L. COPPOCK 2850 </div> </div>	
RECEIVED BY Morrow County Surveyor Date <u>Oct 5 2008</u> Rec'd By <u>SKB</u>		RENEWAL DATE: DEC. 31. 2009	