

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 2 1 1112	TOWNSHIP T 1 N	RANGE R 26 E	
MORROW COUNTY		DATE AUGUST 2008	
CORNER DESIGNATION: 2 1 1112 T 1 N, R 26 E., WILLAMETTE MERIDIAN, MORROW COUNTY, OREGON.			
Previous Renewals / Surveys, etc. ORIGINAL GLO SURVEY BY E. HAFT IN 1861.			
Monument(s) & Accessories Found: (Condition & Source) NO EVIDENCE OF ORIGINAL CORNER FOUND. THERE WAS A ROAD INTERSECTION AND AN OLD FENCE WHICH PERPETUATED THE LOCATION OF THE CORNER LOCATION WHICH I ACCEPTED AS THE BEST EVIDENCE OF THE ORIGINAL LOCATION.			
Monument Detail: <div style="border: 1px solid black; border-radius: 50%; width: 100px; height: 100px; display: flex; align-items: center; justify-content: center; margin: 0 auto;"> T 1 N R 26 E <hr style="width: 50%; margin: 5px 0;"/> 2008 LS 2850 </div> 2 3/8" BRASS CAP ATTACHED TO A 2" X 30" FLARED PIPE.	Sketch: 		
Monument Set (Procedures and Description): 2 3/8" BRASS CAP ATTACHED TO A 2" X 30" FLARED PIPE SET AT INTERSECTION OF LOWER SANDHOLLOW ROAD, MELVILLE LANE AND AN OLD FENCE LINE TO THE SOUTH THAT I ACCEPTED AS THE BEST EVIDENCE OF THE LOCATION OF THE ORIGINAL CORNER. SEE MORROW COUNTY, OREGON PARTITION PLAT 2008-2 DONE BY ME FOR DETAIL.			
New Accessories: BEARING OBJECT SIGN ON POWER POLE BEARS S 79° W 112.76'. BEARING OBJECT SIGN ON GUARD POST FOR A PHONE RISER BEARS N 87° E 355.17'. 2 3/8" BRASS CAP WITNESS CORNER BEARS SOUTH 22.07'. "T" POST WITH WARNING AND BEARING OBJECT SIGNS BEARS SOUTH 23.48'.			
Location & Comments: LOCATED AT INTERSECTION OF LOWER SANDHOLLOW ROAD, MELVILLE LANE AND AN OLD FENCE LINE TO THE SOUTH. 0.4' BELOW SURFACE OF ROAD INTERSECTION.		Compass Declination: NOT DETERMINED	
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836		SURVEYOR'S SEAL REGISTERED PROFESSIONAL LAND SURVEYOR OREGON JANUARY 20 1998 JUDSON L. COPPOCK 2850	
Party Chief JUDSON L. COPPOCK LS 2850 RECEIVED BY			
Notes SHANNON BENEFIT Date <u>Oct 6 2008</u>			
Witness SHANNON BENEFIT Rec'd By <u>SKB</u> No. <u>E-21</u>			
RENEWAL DATE: DEC. 31, 2009			