

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 15 14 22 23	TOWNSHIP T I N	RANGE R 26 E	
MORROW COUNTY		DATE AUGUST 2008	
CORNER DESIGNATION: (Please check one) <input type="checkbox"/> Condition Report Only <input checked="" type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input checked="" type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out			
15 14 T I N. R 26 E OF THE WILLAMETTE 22 23 MERIDIAN, MORROW COUNTY, OREGON.			
Previous Renewals / Surveys, etc. ORIGINAL GLO SURVEY BY E. HAFT IN 1861.			
Monument(s) & Accessories Found: (Condition & Source) NO EVIDENCE OF ORIGINAL CORNER FOUND. THERE WAS A ROAD INTERSECTION WHICH I ACCEPTED AS THE BEST EVIDENCE OF THE ORIGINAL LOCATION AND VERIFIED WITH FURTHER FIELD TIES..			
Monument Detail: <div style="border: 1px solid black; border-radius: 50%; width: 100px; height: 100px; margin: 10px auto; text-align: center; padding: 5px;"> T I N R 26 E 15 14 22 23 2008 LS 2850 </div> 2 3/8" BRASS CAP ATTACHED TO A 2" X 30" FLARED PIPE.	Sketch: 		
Monument Set (Procedures and Description): 2 3/8" BRASS CAP ATTACHED TO A 2" X 30" FLARED PIPE SET AT INTERSECTION OF SANDHOLLOW ROAD AND BARCLAY LANE EXTENDED THAT I ACCEPTED AS THE BEST EVIDENCE OF THE LOCATION OF THE ORIGINAL CORNER. SEE MORROW COUNTY, OREGON PARTITION PLAT 2008-2 DONE BY ME FOR DETAIL.			
New Accessories: POWER POLE WITH BEARING OBJECT SIGN BEARS N 05°54' E 242.49'. POWER POLE WITH BEARING OBJECT AND WARNING SIGN BEARS S 63°51' E 24.26'. POWER POLE WITH BEARING OBJECT SIGN BEARS S 05°00' E 228.08'. POWER POLE WITH BEARING OBJECT SIGN BEARS S 63°08' W 24.96'.			
Location & Comments: LOCATED NEAR INTERSECTION OF SANDHOLLOW ROAD AND MELVILLE LANE AT THE WESTERLY EXTENSION OF THE EAST- WEST PORTION OF MELVILLE LANE. SET BRASS CAP AT SURFACE OF ASPHALT.		Compass Declination: NOT DETERMINED	
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836			
Party Chief JUDSON L. COPPOCK LS 2850			
Notes SHANNON BENEFIT			
Witness SHANNON BENEFIT			

SURVEYOR'S SEAL

REGISTERED PROFESSIONAL LAND SURVEYOR

Judson L. Coppock
 OREGON
 JANUARY 20 1998
 JUDSON L. COPPOCK
 2850

RENEWAL DATE: DEC. 31, 2009

RECEIVED

Morrow County Surveyor

Date Oct 8 2008
 Rec'd By SKB
 No. N-17

N-17