

OREGON CORNER RESTORATION FORM

SECTION 3
COUNTY: MORROW

TOWNSHIP 1 SOUTH
DATE: 7/07/2022

RANGE 24 EAST

CORNER DESIGNATION: A-15

PREVIOUS RENEWALS / SURVEYS, etc.

NO HISTORY OF MONUMENT BEING ESTABLISHED

MONUMENT and ACCESSORIES FOUND: (CONDITION AND SOURCE)

2022: NO EVIDENCE OF CORNER FOUND.

(SEE MORROW COUNTY SURVEY 2022-1994C)

DIAGRAM:



MONUMENT and ACCESSORIES SET (PROCEDURES and DESCRIPTION)

SET 5/8"X30" REBAR W/ 2" ALUMINUM CAP STAMPED AS SHOWN ABOVE AT SOUTH BASE OF E-W FENCE MARKING BOUNDARY OF BASELINE. SET CARSONITE ±0.4' NORTH

(SEE MORROW COUNTY SURVEY 2022-1994C)

REFERENCES SET:

RP-1 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S89°55'57"E 19.31 FEET
RP-2 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S47°35'11"E 30.23 FEET
RP-3 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S27°43'25"W 22.79 FEET
RP-4 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S89°39'32"W 21.63 FEET

LOCATION and COMMENTS

CORNER IS LOCATED APPROXIMATELY 350 FEET EAST OF ELLA ROAD

SURVEYORS SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
MARCH 09, 2021
BRENTON A. GRIFFIN
93754PLS

RENEWALS: 06/30/2023

7/7/22

RECEIVED BY:

MORROW COUNTY SURVEYOR

DATE 8-11-2022

REC'D BY: MOK

NO. 1524A15

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.
1455 COLUMBIA PARK TRAIL, #201
RICHLAND, WA 99352
(509) 783-4141