

OREGON CORNER RESTORATION FORM

SECTION 10

TOWNSHIP 1 SOUTH

RANGE 24 EAST

COUNTY: MORROW

DATE: 7/07/2022

CORNER DESIGNATION: E-15

PREVIOUS RENEWALS / SURVEYS, etc.


1865: ORIGINAL GLO SURVEY, U.S. DEPUTY SURVEYOR DAVID P. THOMPSON SET A POST FOR 1/4 CORNER IN MOUND OF EARTH WITH CHARRED STAKE. PITS AS PER INSTRUCTIONS

MONUMENT and ACCESSORIES FOUND: (CONDITION AND SOURCE)

2022: NO EVIDENCE OF CORNER FOUND.

(SEE MORROW COUNTY SURVEY 2022-1994C)

DIAGRAM:



MONUMENT and ACCESSORIES SET (PROCEDURES and DESCRIPTION)

SET 5/8"X30" REBAR W/ 2" ALUMINUM CAP ±1.3' BELOW GROUND AT NORTH EDGE OF FIELD. STAMPED AS SHOWN ABOVE.

(SEE MORROW COUNTY SURVEY 2022-1994C)

REFERENCES SET:

- RP-1 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" N86°33'40"W 24.10 FEET
- RP-2 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" N24°05'16"W 40.15 FEET
- RP-3 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" N56°52'24"E 37.62 FEET
- RP-4 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S78°07'03"E 23.67 FEET

LOCATION and COMMENTS

CORNER IS LOCATED APPROXIMATELY 50 FEET SOUTH OF THE SOUTH BANK OF WILLOW CREEK AT NORTH EDGE OF FIELD APPROXIMATELY 1100 FEET WEST OF A BRIDGE CROSSING WILLOW CREEK.

SURVEYORS SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Brenton A. Griffin

OREGON
MARCH 09, 2021
BRENTON A. GRIFFIN
93754PLS

RENEWS: 06/30/2023

7/7/22

RECEIVED BY:

MORROW COUNTY SURVEYOR

DATE 8-11-2022

REC'D BY: MPK

NO. 1524E15

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.
1455 COLUMBIA PARK TRAIL, #201
RICHLAND, WA 99352
(509) 783-4141