

# OREGON CORNER RESTORATION FORM

SECTION 10  
COUNTY: MORROW

TOWNSHIP 1 SOUTH  
DATE: 7/07/2022

RANGE 24 EAST

CORNER DESIGNATION: E-17

PREVIOUS RENEWALS / SURVEYS, etc.

1865: ORIGINAL GLO SURVEY, U.S. DEPUTY SURVEYOR DAVID P. THOMPSON SET A POST FOR CORNER OF SECTIONS 2, 3, 10 & 11 IN MOUND OF EARTH WITH CHARRED STAKE. PITS AS PER INSTRUCTIONS.

1909: MORROW COUNTY SURVEY 1173A, D.V. REID DID NOT FIND POST. HE SET A ROCK 18x10x8 MARKED C.S. AT POST TO FENCES RUNNING WEST AND NORTH AS ACCEPTED CORNER POSITION.

1927: O.W.R.&N.Co MAP V-ORE-08-8 HAS A TIE TO SECTION CORNER FROM THE CENTERLINE OF THE TRACK.

1931: ODOT MAP 4B-2-4 HAS A TIE TO SECTION CORNER FROM THE CENTERLINE OF HEPNER HWY.


1979: MORROW COUNTY SURVEY 2015-1744C, W.E. GILLESPIE SHOWS CORNER POSITION BUT DOES NOT STATE FINDING MONUMENT.

MONUMENT and ACCESSORIES FOUND: ( CONDITION AND SOURCE )

2022: NO EVIDENCE OF CORNER FOUND.

(SEE MORROW COUNTY SURVEY 2022-1994C)

DIAGRAM:



MONUMENT and ACCESSORIES SET ( PROCEDURES and DESCRIPTION )

SET 5/8"X30" REBAR W/ 2" ALUMINUM CAP, ±1.5' BELOW GROUND. STAMPED AS SHOWN ABOVE.

(SEE MORROW COUNTY SURVEY 2022-1994C)

REFERENCES SET:

- RP-1 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" N7°56'49"E 20.11 FEET
- RP-2 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" N85°55'44"E 65.02 FEET
- RP-3 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S25°51'32"E 129.08 FEET
- RP-4 SET 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "RSI CONTROL" S35°15'47"W 113.97 FEET

LOCATION and COMMENTS

CORNER FALLS IN CATTLE PEN. ACCESSORIES SET ON OUTSIDE FACES OF FENCES.

SURVEYORS SEAL

RECEIVED BY:

MORROW COUNTY SURVEYOR

DATE 8-11-2022

REC'D BY: MPK

NO. 1524E17

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.  
1455 COLUMBIA PARK TRAIL, #201  
RICHLAND, WA 99352  
(509) 783-4141

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
MARCH 09, 2021  
BRENTON A. GRIFFIN  
93754PLS

RENEWS: 06/30/2023

7/7/22