

OREGON CORNER RESTORATION FORM

SECTION 10

TOWNSHIP 1 SOUTH

RANGE 24 EAST

COUNTY: MORROW

DATE: 7/07/2022

CORNER DESIGNATION: J-15

PREVIOUS RENEWALS / SURVEYS, etc.

1865: ORIGINAL GLO SURVEY, U.S. DEPUTY SURVEYOR DAVID P. THOMPSON SET A STONE 17x7x6 FOR 1/4 CORNER.


1982: MORROW COUNTY SURVEY 2015-1730D, DAVID L. TUTTLE FOUND "STONE MKD. 1/4"

MONUMENT and ACCESSORIES FOUND: (CONDITION AND SOURCE)

2022: NO EVIDENCE WAS FOUND OF THE "STONE MKD. 1/4" PER TUTTLE. FOUND A 2"x2" WOODEN HUB IN A 4FT DIAMETER MOUND OF STONE.

(SEE MORROW COUNTY SURVEY 2022-1994C)

DIAGRAM:



MONUMENT and ACCESSORIES SET (PROCEDURES and DESCRIPTION)

CORNER WAS RE-ESTABLISHED AT POSITION OF 2"x2" WOODEN HUB.
SET A 2" DIAM. BRASS CAP ON 5/8"x24" REBAR STAMPED AS SHOWN ABOVE.

(SEE MORROW COUNTY SURVEY 2022-1994C)

REFERENCES SET:

- RP-1 SET RAILROAD SPIKE N18°37'43"E 10.58 FEET
- RP-2 SET RAILROAD SPIKE S87°35'55"E 20.31 FEET
- RP-3 SET RAILROAD SPIKE S23°58'10"W 8.21 FEET
- RP-4 SET RAILROAD SPIKE S77°59'20"W 13.05 FEET

LOCATION and COMMENTS

CORNER IS LOCATED APPROXIMATELY 1200 FEET NORTH OF CELL TOWER SITE IN SECTION 15, T1S, R24E

SURVEYORS SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
MARCH 09, 2021
BRENTON A. GRIFFIN
93754PLS

RENEWS: 06/30/2023

7/7/22

RECEIVED BY:

MORROW COUNTY SURVEYOR

DATE 8-11-2022

REC'D BY: MAK

NO. 1524515

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.
1455 COLUMBIA PARK TRAIL, #201
RICHLAND, WA 99352
(509) 783-4141