

OREGON CORNER RESTORATION FORM

COUNTY: Morrow

DATE: February 11, 2002

CORNER DESIGNATION: V13(T.1S., R.24E.)

PREVIOUS RENEWAL/SURVEYS ETC: This corner was originally established by David P. Thompson under G.L.O. contract No. 109, dated January 30, 1865. Original Notes state: "80.00 Set post for corner to Sec.s 33, 34, 27 & 28 in mound of earth with charred stake, pits as per instructions."

MONUMENTATION AND ACCESSORIES FOUND: No original evidence of this corner was found. The location of this corner is re-established from an exception in Morrow County Deed Record M9402, reserving a 50 ft. x 50 ft. tract for a reservoir site. This exception calls the SW corner of this tract 8.33 chains south and 3.36 chains east of the corner to Sections 27, 28, 33 & 34. A 16 ft. square fenced area with a well head in the center is field tied. Using the well head as the center of the reserved tract, the position of the corner is determined. See Survey Plat.

MONUMENT MARKING DETAIL:

T1S R24E

S291S28

S321S33

2002

PLS 49865

MONUMENT SET: At the position described above, set 1-1/2"dia x30" iron pipe with 2-1/2" dia. brass cap 1.4' below the ground surface, stamped as shown above, from which:

A 5/8"x30" rebar pin w\yellow plastic cap stamped "F.S. & E. SURVEY MARKER" 1 ft. below the ground surface, bears N38°15'W, 10.20 ft. (Mag. Compass, 20°30' Decl)

A 5/8"x30" rebar pin w\yellow plastic cap stamped "F.S. & E. SURVEY MARKER" 1 ft. below the ground surface, bears N70°00'E, 10.00 ft. (Mag. Compass, 20°30' Decl)

A 5/8"x30" rebar pin w\yellow plastic cap stamped "F.S. & E. SURVEY MARKER" 1 ft. below the ground surface, bears S38°45'E, 9.80 ft. (Mag. Compass, 20°30' Decl)

A 5/8"x30" rebar pin w\yellow plastic cap stamped "F.S. & E. SURVEY MARKER" 1 ft. below the ground surface, bears S54°00'W, 9.80 ft. (Mag. Compass, 20°30' Decl)

LOCATION: Corner is in a cultivated field and is buried as described above.

FIRM:

Ferguson Surveying & Engineering
210 E. Main, P.O. 519
Mt. Vernon, OR 97865
Ph. (541)932-4520
Fax(541)932-4430

Witnesses:

D. Mitchell Ferguson
Brad Cates

Surveyor's Seal

RECEIVED BY
Morrow County Surveyor

Date: 1-4-14
Recd By: S.K.H.
No.: 1524V13
Folder No.: _____



Renews 01/01/2004