

# OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: February 11, 2002

CORNER DESIGNATION: V9 (T.1S., R.24E.)

**PREVIOUS RENEWAL/SURVEYS ETC:** This corner was originally established by David P. Thompson under G.L.O. contract No. 109, dated January 30, 1865. Original Notes state: "80.00 Set post for corner to Sec.s 28, 29, 32 & 33 in mound of earth with charred stake, pits as per instructions."

**MONUMENTATION AND ACCESSORIES FOUND:** No original evidence of this corner was found. A long standing fence corner (north & east) is accepted as the best available evidence of this corner location based on it's near record relationship to the corner one mile to the east and it's harmonious relationship with surrounding, long standing lines of occupancy (fences). See Survey Plat.

### MONUMENT MARKING DETAIL:

T1S R24E  
S29|S28  
---  
S32|S33  
2002  
PLS 49865

**MONUMENT SET:** At the position described above, set 1-1/2" dia x30" iron pipe with 2-1/2" dia. brass cap 26" in the ground, stamped as shown above, from which:

A 5/8"x30" rebar pin w\1-1/2" dia. alum. cap stamped "MCRW 47+61, 30 ft., F.S. & E. bears N0°19'51"E, 30.00 ft. (by Survey)

A 5/8"x30" rebar pin w\1-1/2" dia. alum. cap stamped "MCRW 47+61, 30 ft., F.S. & E. bears S0°19'51"W, 30.00 ft. (by Survey)

A 5/8"x30" rebar pin w\yellow plastic cap stamped "F.S. & E. SURVEY MARKER" bears S49°W, 10.80 ft. (Mag. Compass, 20°30' Decl)

A 5/8"x30" rebar pin w\yellow plastic cap stamped "F.S. & E. SURVEY MARKER" bears N54°45'E, 10.45 ft. (Mag. Compass, 20°30' Decl)

**LOCATION:** Corner is located 5' north of the existing edge of Morter Rd. (Co. Rd. 576) and 2" north of a 1'x8" railroad tie fence corner post.

### FIRM: Ferguson Surveying & Engineering

210 E. Main, P.O. 519  
Mt. Vernon, OR 97865  
Ph. (541)932-4520  
Fax(541)932-4430

**Witnesses:** D. Mitchell Ferguson  
Brad Cates

Surveyor's Seal

RECEIVED BY  
Morrow County Surveyor

Date: 1-4-14  
Recd By: S.K.H.  
No.: 1524 V9  
Folder No.: \_\_\_\_\_



Renews 01/01/2004