

# OREGON CORNER RESTORATION FORM

SECTION 27

TOWNSHIP 1 SOUTH

RANGE 25 EAST

COUNTY: MORROW

DATE: 09/15/2015

CORNER DESIGNATION: T-17

PREVIOUS RENEWALS / SURVEYS, etc.


ORIGINAL CORNER SET BY U.S. DEPUTY SURVEYOR DAVID P. THOMPSON IN 1865.

DAVID KRUMBEIN, PLS 933, DENOTES SETTING A BRASS CAP AT THIS CORNER AS SHOWN COUNTY SURVEY D-623-K, DATED 6/15/83

MONUMENT and ACCESSORIES FOUND: ( CONDITION AND SOURCE )

NO EVIDENCE WAS FOUND OF THE KRUMBEIN BRASS CAP. MONUMENT WAS APPARENTLY DESTROYED.

DIAGRAM:



MONUMENT and ACCESSORIES SET ( PROCEDURES and DESCRIPTION )

CORNER WAS RE-ESTABLISHED FROM RECORD POSITION PER SURVEY D-623-K, MORROW COUNTY SURVEY RECORDS. SET 2-1/2" DIAM. BRASS CAP ON 1"X30" GALVANIZED IRON PIPE STAMPED AS SHOWN ABOVE. MONUMENT FALLS 1.8' SOUTH OF CORNER OF FENCES BEARING SOUTH AND WEST.

REFERENCES SET:

- RP-1 SET 5/8"x30" REBAR NORTH 101.49 FEET
- RP-2 SET 5/8"x30" REBAR EAST 25.89 FEET
- RP-3 SET 5/8" REBAR SOUTH 32.68 FEET
- RP-4 SET 5/8" REBAR WEST 35.03 FEET

LOCATION and COMMENTS

CORNER IS LOCATED APPROXIMATELY 830' FEET EAST OF STATE HIGHWAY 207 NEAR THE SOUTHEAST CORNER OF THE LEXINGTON AIRPORT

SURVEYORS SEAL



RECEIVED BY:

MORROW COUNTY SURVEYOR

DATE 9-16-2015

REC'D BY: S.K.H.

NO. 1525T17

Survey C-1348-M

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.  
1455 COLUMBIA PARK TRAIL, #201  
RICHLAND, WA 99352  
(509) 783-4141