

X-3

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT
MORROW COUNTY SURVEYOR'S OFFICE

SECTION 1/4 32/33	TOWNSHIP T 1 S	RANGE R 25 E														
MORROW COUNTY, OREGON																
CORNER DESIGNATION: 1/4 CORNER COMMON TO SECTIONS 32 AND 33, T 1 S, R 25 E OF THE WILLAMETTE MERIDIAN, MORROW COUNTY, OREGON.		DATE: 2 MAY 2006														
Previous Renewals / Surveys, etc.																
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td align="center" colspan="2">(Please check one)</td> </tr> <tr> <td><input type="checkbox"/> Condition Report Only</td> <td></td> </tr> <tr> <td><input type="checkbox"/> Not Found</td> <td></td> </tr> <tr> <td><input type="checkbox"/> Renewed</td> <td></td> </tr> <tr> <td><input type="checkbox"/> Unrecorded</td> <td></td> </tr> <tr> <td><input type="checkbox"/> Surveyed In</td> <td></td> </tr> <tr> <td><input checked="" type="checkbox"/> Referenced Out</td> <td></td> </tr> </table>			(Please check one)		<input type="checkbox"/> Condition Report Only		<input type="checkbox"/> Not Found		<input type="checkbox"/> Renewed		<input type="checkbox"/> Unrecorded		<input type="checkbox"/> Surveyed In		<input checked="" type="checkbox"/> Referenced Out	
(Please check one)																
<input type="checkbox"/> Condition Report Only																
<input type="checkbox"/> Not Found																
<input type="checkbox"/> Renewed																
<input type="checkbox"/> Unrecorded																
<input type="checkbox"/> Surveyed In																
<input checked="" type="checkbox"/> Referenced Out																
CHARRED STAKE SET BY THOMPSON. GLO CONTRACT 119, 15 FEB. 1867.																
Monument(s) & Accessories Found: (Condition & Source) ROCK CRIB AT END OF EAST-WEST FENCE, C/L OF COUNTY ROAD.																
Monument Detail: <div style="text-align: center; border: 1px solid black; border-radius: 50%; width: 100px; height: 100px; margin: 0 auto; display: flex; flex-direction: column; align-items: center; justify-content: center;"> <p>T 1 S R 25 E</p> <p>1/4 32/33</p> <p>2006</p> <p>LS 2850</p> </div> 2 3/8" BRASS CAP ON A 2" ID X 30" FLAIED GALV. STEEL PIPE.	Sketch: 															
Monument Set (Procedures and Description): SET 2 3/8" BRASS CAP STAMPED AS SHOWN ON 2" ID X 30 FLAIED GALV. STEEL PIPE. ACCEPTED LOCATION OF ROCK JACK AS BEST AVAILABLE EVIDENCE OF ORIGINAL LOCATION.																
New Accessories: SET 1/2" GALV PIPE N 66° W 96.83' WITH " T " POST GUARD, WITH BEARING OBJECT SIGN. SET A 3/4" SQ. ROD WEEDER SHAFT S 4° W 56.48' WITH " T " POST GUARD, WITH OBJECT SIGN. SET " T " POST WITH BEARING OBJECT SIGN S 5° E 20.85'. SET " T " POST WITH BEARING OBJECT SIGN EAST 0.25'.																
Location & Comments: AT END OF EAST-WEST FENCE AND EASY ACCESS		Compass Declination: NOT DETERMINED														
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836																
Party Chief JUDSON L. COPPOCK LS 2850																
Notes SHANNON BENEFIT																
Witness																
SURVEYOR'S SEAL		<div style="border: 1px solid black; padding: 5px; text-align: center;"> REGISTERED PROFESSIONAL LAND SURVEYOR </div> <div style="text-align: center;"> <small>OREGON JANUARY 20 1988 JUDSON L. COPPOCK 2850</small> </div>														
		RENEWAL DATE: DEC. 31, 2007														

X-9