

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 1/4 $\frac{34}{3}$	TOWNSHIP $\frac{T 1 S}{T 2 S}$	RANGE R 25 E, W.M.
MORROW COUNTY, OREGON		DATE: 3 MAY 2006
CORNER DESIGNATION:  S 1/4 CORNER OF SECTION 34, T 1 S, R 25 E, W.M. N 1/4 CORNER OF SECTION 3, T 2 S, R 25 E, W.M.		
Previous Renewals / Surveys, etc. GLO CONTRACT 119, 15 FEB. 1867 BY THOMPSON AND PENGRA SET CHARRED STAKE.		
Monument(s) & Accessories Found: (Condition & Source) NO EVIDENCE OTHER THAN AN E-W FENCE TO THE EAST AND FLOW LINE WEST, ALSO A N-S COUNTY ROAD.		
Monument Detail: <div style="border: 1px solid black; border-radius: 50%; width: 80px; height: 80px; margin: 10px auto; text-align: center; padding: 5px;">                     T 1 S R 25 E                      1/4 <math>\frac{34}{3}</math>                      T 2 S R 25 E                      2006                      LS 2850                 </div> 2 3/8" BRASS CAP ON A 2" ID X 30" FLAIED STEEP PIPE 0.1' BELOW SURFACE OF ROAD.	Sketch: 	
Monument Set (Procedures and Description): SET 2 3/8" BRASS CAP STAMPED AS SHOWN ON A 2" ID X 30" FLAIED STEEL PIPE 01' BELOW THE SURFACE OF COUNTY ROAD. PROPORTIONED IN BY SURVEY.		
New Accessories: SET A 1/2" ID X 24" GALV PIPE N 89° 58' W 30.00' PLACED A BEARING OBJECT SIGN ON A EXISTING FENCE POST N 22° 48' W 80.84'. SET A 1/2" ID X 24" GALV. PIPE S 89° 58' E 30.00'. PLACED A BEARING OBJECT SIGN ON AN EXISTING FENCE POST S 12° 45' E 114.43'.		
Location & Comments:  CORNER FALLS IN COUNTY ROAD. EASY ACCESS.		Compass Declination:  NOT DETERMINED
Firm / Agency COPPOCK SURVEYING PO Box 495 HEPNER, OR 97836		
Party Chief JUDSON L. COPPOCK LS 2850		
Notes SHANNON BENEFIT		
Witness		
SURVEYOR'S SEAL REGISTERED PROFESSIONAL LAND SURVEYOR OREGON JANUARY 20 1988 JUDSON L. COPPOCK 2850		RENEWAL DATE: DEC. 31, 2007