

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION 34   35 3   2	TOWNSHIP T 1 S T 2 S	RANGE R 25 E
MORROW COUNTY, OREGON		
DATE: 3 MAY 2006		
CORNER DESIGNATION: (Please check one)		
SECTION CORNER COMMON TO SECTIONS 34 AND 35, T 1 S, R 25 E AND SECTIONS 3 AND 2, T 2 S, R 25 E., WILLAMETTE MERIDIAN, MORROW COUNTY, OREGON.		
<input type="checkbox"/> Condition Report Only <input checked="" type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out		
Previous Renewals / Surveys, etc.		
GLO CONTRACT 119, 15 FEB. 1867 BY THOMPSON AND PENGRA. POST AND CHARRED STAKE SET.		
Monument(s) & Accessories Found: (Condition & Source)  FENCE CORNER ONLY		
<b>Monument Detail:</b>  <div style="border: 1px solid black; border-radius: 50%; width: 80px; height: 80px; margin: 0 auto; display: flex; flex-direction: column; align-items: center; justify-content: center; text-align: center;"> <div style="font-size: 8px; margin-bottom: 2px;">2005</div> <div style="font-size: 8px; margin-bottom: 2px;">T 1 S, R 25 E</div> <div style="font-size: 8px; margin-bottom: 2px;">34   35</div> <div style="font-size: 8px; margin-bottom: 2px;">3   2</div> <div style="font-size: 8px; margin-bottom: 2px;">T 2 S, R 25 E</div> <div style="font-size: 8px; margin-bottom: 2px;">LS 2850</div> </div> 2 3/8" BRASS CAP STAMPED AS SHOWN ON A 2" ID X 30" FLARED STEEL PIPE.	<b>Sketch:</b> 	
<b>Monument Set (Procedures and Description):</b> SET BRASS CAP STAMPED AS SHOWN AT FENCE CORNER ACCEPTED AS THE BEST REMAINING EVIDENCE OF ORIGINAL CORNER LOCATION.		
<b>New Accessories:</b> PLACED BEARING OBJECT ON EXISTING R/R TIE FENCE POST WHICH BEARS WEST 74.95°. PLACED WARNING AND BEARING OBJECT SIGN ON EXISTING R/R TIE FENCE POST WHICH BEARS S 15° W 0.40'. SET " T " POST WITH BEARING OBJECT SIGN SOUTH 7.27'. SET A 5/8" X 30" STEEL REBAR WITH A PLASTIC CAP STAMPED LS 2850 N 45° E 2.95' AND 1 FOOT BELOW SURFACE.		
<b>Location &amp; Comments:</b> AT FENCE CORNER AND SURROUNDED BY CRP AND CROW LAND. NO ROAD ACCESS.		
<b>Compass Declination:</b> NOT DETERMINED		
<b>Firm / Agency</b> COPPOCK SURVEYING PO Box 495 HEPNER, OR 97836		
<b>Party Chief</b> JUDSON L. COPPOCK LS 2850		
<b>Notes</b> SHANNON BENEFIT		
<b>Witness</b>		
<b>SURVEYOR'S SEAL</b> REGISTERED PROFESSIONAL LAND SURVEYOR		OREGON JANUARY 20 1988 JUDSON L. COPPOCK 2850
RENEWAL DATE: DEC. 31, 2007		