

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Corner Code No. 2-5
Notes: Monument marked as shown below

T 1S, R 27E., W.M.

History of original corner establishment:

This corner was originally established by Thompson and Pengra, U.S. Deputy Surveyors, under Joint Contract No. 119, dated February 15, 1881.

The original notes state:

Set post for corner to Secs. 5, 6, 31 & 32 in mound of earth with charred stake and pits as per instructions.

DIAGRAM	
11S R27E	
531 532	
5 6 5 5	
12S R27E	

Compass No. _____
Compass Declination: 18.0°

Description of corner evidence found:

Ancient fence corner with fences going East, West and South from corner.

This position was confirmed by survey and aerial photograph measurements to nearby fence and field lines.

A 3" "square nail" spike was found when excavating to place the corner monument. This spike indicates a pre-1900 location for the fence corner.

Description of monument and accessories | established to perpetuate the original location of this corner:

The corner falls in an area where bedrock exists about 12" below ground surface. A conventional brass cap monument would be subject to disturbance because of cattle in the area, so an iron pin monument was driven into the bedrock.

At the above described fence intersection, I drove a 5/8" by 24" iron pin 20" into the ground and bedrock and surrounded with a mound of stone. The iron pin is capped with a 2" aluminum cap, marked as shown in the corner diagram.

Referenced the corner as follows:

- A 3/4" brass washer, nailed to the South side of a unnumbered power pole, 1' above ground, bears N 85 1/2° E 72.0 feet.
- A 5/8" by 30" iron pin with 1 1/2" yellow plastic cap bears S 0 1/2° W 41.6'.
- A 3/4" brass washer, nailed to the North side of a rock jack, 6" above ground, bears West 38.7'.
- A 3/4" brass washer, nailed to the South side of power pole No. 3-6-115 1/2, 1' above ground, bears N 87° W 165.6'.

The 3/4" brass washers are stamped "PLS 1106". The 1 1/2" yellow plastic cap is marked "W.R. Wells, PLS 1106".

Nailed bearing object signs to the power poles and fence jack. Wired bearing object sign to the iron pin reference monument.

Nailed a witness corner sign to the fence jack about 3' East of the corner monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1917
WILLIAM R. WELLS
1106

Office of..... County of *Marion*
State of....., I hereby certify that the within instrument was filed in this office
for record on the *18th* day of *April*, 19*73*
..... by (DEPUTY)

12-31-94 expires