

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT
Morrow County Surveyor's Office

J-9

SECTION	TOWNSHIP 2 NORTH	RANGE R 23 E							
COUNTY: Morrow		DATE DECEMBER 12, 2012							
CORNER DESIGNATION: Corner to sections 8, 9, 17 and 16, T2N, R23E, W.M., Morrow County, Oregon.									
<table style="width: 100%; border: none;"> <tr> <td style="border: none;"><input type="checkbox"/> Condition Report Only</td> </tr> <tr> <td style="border: none;"><input type="checkbox"/> Not Found</td> </tr> <tr> <td style="border: none;"><input type="checkbox"/> Renewed</td> </tr> <tr> <td style="border: none;"><input type="checkbox"/> Unrecorded</td> </tr> <tr> <td style="border: none;"><input checked="" type="checkbox"/> Surveyed In</td> </tr> <tr> <td style="border: none;"><input checked="" type="checkbox"/> Referenced Out</td> </tr> </table> <p>(Please check one)</p>				<input type="checkbox"/> Condition Report Only	<input type="checkbox"/> Not Found	<input type="checkbox"/> Renewed	<input type="checkbox"/> Unrecorded	<input checked="" type="checkbox"/> Surveyed In	<input checked="" type="checkbox"/> Referenced Out
<input type="checkbox"/> Condition Report Only									
<input type="checkbox"/> Not Found									
<input type="checkbox"/> Renewed									
<input type="checkbox"/> Unrecorded									
<input checked="" type="checkbox"/> Surveyed In									
<input checked="" type="checkbox"/> Referenced Out									
Previous Renewals / Surveys, etc. Original Contract #119 in 1867. Thompson & Pengra set post with charred stake as per instructions.									
Monument(s) & Accessories Found: (Condition & Source) No evidence found of original survey.									
Monument Detail: <div style="text-align: center; border: 1px solid black; border-radius: 50%; width: 100px; height: 100px; margin: 0 auto; display: flex; flex-direction: column; align-items: center; justify-content: center;"> T2N R23E 8 9 17 16 2006 LS 2850 </div>		Sketch:							
Monument Set (Procedures and Description): Set 2" I.D. x 30" galvanized pipe with a 2 3/8" Brass Cap.									
New Accessories: From which A 5/8" rebar with plastic cap #2850 bears North 10.19 feet.. A 5/8" rebar with plastic cap #2850 bears East 9.2 feet. A wooden fence post with sign bears West 13.62 feet. A wooden fence post with sign bears South 18.04 feet.									
Location & Comments:		Compass Declination:							
SURVEYOR'S SEAL									
Firm / Agency Coppock Surveying Address: P.O. Box 495 Heppner, OR. 97836 Party Chief Judson L. Coppock									
Notes									
Witness									



Judson L. Coppock

