

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

SECTION	33 34 4 3	TOWNSHIP	T 1 S T 2 S	RANGE	R 25 E., W.M.
MORROW COUNTY, OREGON		DATE: 3 MAY 2006			
CORNER DESIGNATION:					
(Please check one)					
SECTION CORNER COMMON TO SECTIONS 33 AND 34 T 1 S, R 25 E AND SECTIONS 4 AND 3 T 2 S, R 25 E., W.M.					
<input type="checkbox"/> Condition Report Only <input checked="" type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input checked="" type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out					
Previous Renewals / Surveys, etc.					
GLO CONTRACT 119. 15 FEB 1867 BY THOMPSON AND PENGRA. SET POST AND CHARRED STAKE.					
Monument(s) & Accessories Found: (Condition & Source)					
NO EVIDENCE FOUND. PLOW LINE HAS BEEN MIGRATING NORTHWARD AND NOW IS ABOUT 11' TOO FAR NORTH. OLD FENCE LINES TO THE WEST INDICATE THIS SHIFT IS FAIRLY RECENT.					
Monument Detail:			Sketch:		
Monument Set (Procedures and Description):					
SET A 2 3/8" BRASS CAP STAMPED AS SHOWN ON A 2" ID X 30" FLAILED STEEL PIPE OVER A 5/8" X 30 STEEL REBAR WHICH IS 24" BELOW SURFACE.					
New Accessories:					
SET A 5/8" STEEL REBAR 24" DEEP UNDER BRASS CAP MONUMENT. SET A " T " POST WITH WARNING AND BEARING OBJECT SIGNS WEST 0.45'. SET A " T " POST WITH A BEARING OBJECT SIGN NORTH 10.34'. SET A 1 1/4" X 1.8" STEEL SHAFT NORTH 10.69'.					
Location & Comments:			Compass Declination:		
LOCATED ON EDGE OF CROP AND CRP LAND. NO ROAD ACCESS.			NOT DETERMINED		
Firm / Agency		SURVEYOR'S SEAL			
COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836					
Party Chief					
JUDSON L. COPPOCK LS 2850					
Notes		SHANNON BENEFIT			
Witness		RENEWAL DATE: DEC. 31, 2007			