

OREGON PUBLIC LAND CORNER REPORT / RESTORATION REPORT

MORROW COUNTY SURVEYOR'S OFFICE

<b>SECTION</b>	32   33 — 5   4	<b>TOWNSHIP</b>	T 1 S — T 2 S	<b>RANGE</b>	R 25 E
<b>MORROW COUNTY, OREGON</b>		<b>DATE:</b> 3 MAY 2006			
<b>CORNER DESIGNATION:</b>					
(Please check one)					
<input type="checkbox"/> Condition Report Only <input checked="" type="checkbox"/> Not Found <input type="checkbox"/> Renewed <input type="checkbox"/> Unrecorded <input type="checkbox"/> Surveyed In <input checked="" type="checkbox"/> Referenced Out					
SECTION CORNER COMMON TO SECTIONS 32, 33, T 1 S R 25 E AND SECTIONS 5, 4, T 2 S, R 25 E., WILLAMETTE MERIDIAN, MORROW COUNTY, OREGON.					
Previous Renewals / Surveys, etc.					
GLO CONTRACT 119, 15 FEB. 1867 BY THOMPSON AND PENGRA SET POST AND CHARRED STAKE					
<b>Monument(s) &amp; Accessories Found: (Condition &amp; Source)</b>					
FENCE CORNER ONLY. ACCEPTED AS BEST EVIDENCE OF ORIGINAL CORNER REMAINING.					
<b>Monument Detail:</b>	<div style="border: 1px solid black; border-radius: 50%; width: 100px; height: 100px; margin: 0 auto; display: flex; flex-direction: column; align-items: center; justify-content: center; text-align: center;"> <div style="margin-bottom: 5px;">2005</div> <div style="margin-bottom: 5px;">T 1 S R 25 E</div> <div style="margin-bottom: 5px;">32   33</div> <div style="margin-bottom: 5px;">— 5   4</div> <div style="margin-bottom: 5px;">T 2 S R 25 E</div> <div style="margin-bottom: 5px;">LS 2850</div> </div> <p>2 3/8" BRASS CAP STAMPED AS SHOWN ON A 2" ID X 30" FLAIRED STEEL PIPE.</p>				
<b>Sketch:</b>					
<b>Monument Set (Procedures and Description):</b>					
2 3/8" BRASS CAP STAMPED AS SHOWN ON A 2" ID X 30" FLAIRED STEEL PIPE.					
<b>New Accessories:</b>					
SET A 5/8" X 30" STEEL REBAR 1 FOOT BELOW SURFACE NORTHWEST 5.10'. SET A " T " POST WITH BEARING OBJECT SIGN EAST 3.45' PLACED A WARNING SIGN AND A BEARING OBJECT SIGN ON EXISTING WOOD FENCE POST S 34° E 0.75'. PLACED A BEARING OBJECT SIGN ON AN EXISTING FENCE POST SOUTH 6.55'.					
<b>Location &amp; Comments:</b>			<b>Compass Declination:</b>		
AT A FENCE CORNER, THE EASTERLY RUN BEING REMOVED AND ABOUT 150' SOUTHEAST OF A COUNTY ROAD.			NOT DETERMINED		
<b>Firm / Agency</b>					
COPPOCK SURVEYING PO Box 495 HEPPNER, OR 97836					
<b>Party Chief</b>					
JUDSON L. COPPOCK LS 2850					
<b>Notes</b>					
SHANNON BENEFIT					
<b>Witness</b>					
<b>SURVEYOR'S SEAL</b>					
REGISTERED PROFESSIONAL LAND SURVEYOR					
OREGON JANUARY 20 1998 JUDSON L. COPPOCK 2850					
RENEWAL DATE: DEC. 31, 2007					