

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 5/31/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 2, Township 2 South, Range 25 East, W.M., C-17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Thompson and Pengra under Contract 119, dated July 15, 1867. Notes state: Set a stone 22 x 10 x 8 inches, 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: Found a set 20 x 10 x 6 stone with broken top. Held the bottom of the stone as the corner point. I washed the stone with water but could discern no chisel marks. The top of the stone was tipped 6" North.

MONUMENT MARKING DETAIL:

T2S R25E
1/4
S3|S2
2015
PLS 1106

MONUMENT SET:

Stone falls at an old fence corner with old fences West and North and field lines East and South. At the corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, 28" in the ground, stamped as shown in "Monument Marking Detail".

New Accessories:

- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 01° East, 10.2 feet.
- A 5/8" x 24 rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 01° East, 71.8 feet.
- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears West, 28.5 feet.
- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears West, 54.0 feet.

Set steel fence post 1 1/2 feet South of corner with Witness sign attached. Wired bearing object tags to all rebar accessories. Placed found stone flat North of corner monument.

LOCATION AND COMMENTS: At fence corner with old fences West and North and field lines East and South.

OREGON STATE PLANE COORDINATES, North Zone, International Feet, NAD 83-2011,

Epoch 2010.00:
N = 640983.95
E = 8413129.51

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witness: William Wells, PLS

RECEIVED BY
Morrow County Surveyor

Date: 6-30-2015
Rec'd By: SKH
No.: 2015-1743C
Folder No.: 2525 C17

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Willie R. Wells

OREGON
JUL - 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-16