

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 5/31/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 1, Township 2 South, Range 25 East, W.M., C-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Thompson and Pengra under Contract 119, dated July 15, 1867. Notes state: Set charred stake and raised mound as 1/4 Section Corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T2S R25E
1/4
S2|S1
2015
PLS 1106

MONUMENT SET:

I held the projected intersection of fence lines extending West and South as best remaining evidence of the original corner location, after verifying position by survey. At the reestablished corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, 23" in the ground to caliche rock and surrounded with a mound of earth. Cap is stamped as shown in "Monument Marking Detail".

New Accessories:

- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North, 34.3 feet. Wired bearing object tag to rebar.
 - A 3/4" brass washer stamped "PLS 1106", on South side of power pole, 1 foot above ground level, bears South 01° East, 26.7 feet. Nailed bearing object tag to the pole.
 - A 5/8" x 24" rebar with a blue plastic cap stamped "OR PLS 1106, WA PLS 17372", by gate post, bears South 64° West, 19.9 feet. Wired bearing object tag to the rebar.
 - A 5/8" x 24" rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", set in East-West fence line, bears North 89° West, 93.4 feet. Wired bearing object tag to the rebar.
- Set steel fence post 1 1/2 feet South of corner with Witness sign attached.

LOCATION AND COMMENTS: At projection of fence from South with fence and field line extending West. There is a field gate near the corner monument.

OREGON STATE PLANE COORDINATES, North Zone, International Feet, NAD 83-2011, Epoch 2010.00:

N = 641031.31
E = 8418338.75

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: William Wells, PLS

2S25C21
RECEIVED BY
Morrow County Surveyor

Date: 6-30-15
Rec'd By: SKH
No.: 2015-1743C
Folder No.: 2S25C21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JUL 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-16