

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 6/1/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 12, Township 2 South, Range 25 East, W.M., G-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Thompson and Pengra under Contract 119, dated July 15, 1867. Notes state: Set a stone 16 x 9 x 7 inches as 1/4 section corner.

MONUMENT AND ACCESSORIES FOUND: None. Dennis Edwards, on Partition Plat No. 1996-4, (Survey No. C-1088-E), set a "P.K" nail at approximate 1/4 corner. Since Partition Plat No. 1996-4, the asphalt surface of Meadow Brook Road has been graded off and replaced with a gravel surface.

MONUMENT MARKING DETAIL:

T2S R25E
1/4
S11|S12
2015
PLS 1106

MONUMENT SET:

I re-established the position of the Edwards "P.K." by distance-distance intersection from the railroad spike set by Edwards near the Center 1/4 corner of Section 11 and the railroad spike set by Edwards as the approximate SE corner of Section 11. The point falls in the centerline of gravel County Roads extending North-South and West and an old fence line extends East. I held the position of the Edwards "P.K." as the corner point and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 6" below road surface, stamped as shown in "Monument Marking Detail".

New Accessories:

- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 29° East, 52.5 feet. Wired bearing object tag to rebar.
- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 89° East, 25.0 feet. Rebar is just West of railroad tie fence corner with fences extending North-South and East. Nailed bearing object tag to railroad tie post.
- A 3/4" brass washer, stamped "PLS 1106", 1.5 feet above ground level on a power pole, bears South 35° East, 34.2 feet, nailed bearing object tag to pole.
- A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 28° West, 65.6 feet. Wired bearing object tag to rebar.

LOCATION AND COMMENTS: In gravel road North-South-West and at intersection of fence extending East.

OREGON STATE PLANE COORDINATES, North Zone, International Feet NAD 83-2011, Epoch 2010.00:

N = 635774.91
E = 8418413.11

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: William R. Wells, PLS

Dean Roy

√2S25G21

RECEIVED BY

Morrow County Surveyor

Date: 6-30-15


Rec'd By: SKH

No.: 2015-1743C

Folder No.: 2525G 21



William R. Wells



renews 6-30-16