

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 5/31/15

CORNER DESIGNATION: The Northwest Corner of Section 13, Township 2 South, Range 25 East, W.M., J-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Thompson and Pengra under Contract 119, dated July 15, 1867. Notes state: Drove charred stake and raised mound as corner to Sections 11, 12, 13 & 14.

MONUMENT AND ACCESSORIES FOUND: Found a railroad spike 6" below road surface set by Dennis Edwards on Partition Plat No. 1996-14, (Survey No. C-1088-E). Edwards set the railroad spike in the centerline of North-South Meadow Brook Road with a old fence line extending West. Edwards calls this the "approximate sec. corner".

MONUMENT MARKING DETAIL:

T2S R25E

S11|S12

S14|S13

2015

PLS 1106

MONUMENT SET:

I recovered the Edwards railroad spike and held it as the best remaining evidence of the original corner point. In digging in the new corner monument, I hit caliche rock 19 inches below the road surface and could dig no further. I hammered a 30" rebar about 2" into the caliche, pulled it out and set a 15" rebar in the hole with 2" aluminum cap, marked as shown in "Monument Marking Detail". The aluminum cap is 6" below the road surface.

New Accessories:

A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", set in North-South right-of-way fence bears North 47° East, 33.9 feet. Wired bearing object tag to rebar.

A 3/4" brass washer, stamped "PLS 1106", nailed to power pole on West side 1 foot above ground level bears East, 20.1 feet. Attached bearing object and Witness sign to pole.

A 5/8" x 24" rebar with a red plastic cap stamped "OR PLS 1106, WA PLS 17372", set 1 1/2 feet West of North-South right-of-way fence and at North side of a large rock, bears South 28° East, 46.2 feet.

A 3/4" brass washer stamped "PLS 1106" nailed to Northeast post of 4 post square fence jack, bears West, 28.6 feet. Washer is 1 foot above ground level facing corner. Nailed bearing object tag to the fence jack.

Laid Edwards railroad spike flat on South side of corner monument, 6" below road surface, as a memorial.

LOCATION AND COMMENTS: Corner located in the center of Meadow Brook Road. An old fence line extends West. A house is located NW of the corner.

OREGON STATE PLANE COORDINATES, North Zone, International Feet, NAD 83-2011,

Epoch 2010.00:

N = 633142.83

E = 8418453.05

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: William Wells, PLS

RECEIVED BY

Morrow County Surveyor

\2S25J21

Date: 6-30-2015

Rec'd By: SKH

No.: 2015-1743C

Folder No.: 2 S 25 J 21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-16