

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 13
DIAGRAM

| |
|----------------|
| T2S R29E |
| <u>S16 S15</u> |
| <u>S21 S22</u> |
| PLS 1636 |
| 2004 |

History of original corner establishment:

The original corner was established by George S. Pershin on September 16, 1871, under GLO contract No. 154, as follows:

Set a stone, 20" x 12" x 8", on east hillside for corner to sections 15, 16, 21 and 22.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The original corner stone is 19" x 11" x 6" and is plainly marked with two notches on one (east) edge and two notches on another (north) edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 17" into the ground to bedrock. I bury the corner stone along the southwest side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 15", attached at ground level, bears N42° E, 113.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 22", attached at ground level, bears S46° 30' E, 98.1 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 21", attached at ground level, bears S52° 30' W, 107.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 16", attached at ground level, bears N32° 30' W, 131.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 22, 2004. Magnetic declination set in compass: 18° E.
NAD '83 UTM Zone 11 position: 5028187N, 327125E (plus or minus two meters).

RECEIVED BY
Morrow County Surveyor

Date: 1-4-2014
Recd By: S.K.H.
No.: 2529 N13
Folder No.: _____



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: