

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P - 21  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 13, 1871, under GLO contract No. 154, as follows:

Set a stone, 22" x 8" x 5", on southwest hillside for the 1/4 section corner to sections 23 and 24.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 20" x 9" x 5" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 17" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N65° 30' E, 74.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S61° E, 65.2 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S45° W, 83.8 feet. This reference is west of, and across a draw from the corner point.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N48° 30' W, 133.8 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 25, 2004. Magnetic declination set in compass: 18° E.  
NAD '83 UTM Zone 11 position: 5027284N, 330371E (plus or minus two meters).

RECEIVED BY  
Morrow County Surveyor

*Dennis L. Gaylord*

Date: 1-4-14  
Rec'd By: S.K.H.  
No.: 2529 P21  
Folder No.: \_\_\_\_\_



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: