

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 13
DIAGRAM



History of original corner establishment:

The original corner was established by George S. Pershin on September 16, 1871, under GLO contract No. 154, as follows:

Set a stone, 18" x 10" x 5", on west hillside for corner to sections 21, 22, 27 and 28.

Original corner evidence recovered:

Found the original corner stone solidly set on the west edge of a mound of stones. The original corner stone is 17" x 8" x 7" and is plainly marked with two notches on the west edge and one notch on the north edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 22", attached at ground level, bears N48° E, 111.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 27", attached at ground level, bears S60° E, 103.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 28", attached at ground level, bears S44° W, 116.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 21", attached at ground level, bears N34° W, 90.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 22, 2004. Magnetic declination set in compass: 18° E.
NAD '83 UTM Zone 11 position: 5026575N, 327079E (plus or minus two meters).

RECEIVED BY
Morrow County Surveyor

[Signature]



Date: 1-4-14
Rec'd By: S.K.H.
No.: 2529 R13
Folder No.: _____

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: