

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 15
DIAGRAM



History of original corner establishment:

The original corner was established by George S. Pershin on September 16, 1871, under GLO contract No. 154, as follows:

Set a stone, 20" x 14" x 10", on southwest side of spur for the 1/4 section corner to sections 22 and 27.

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 20" x 13" x 8" and is marked "1/4" on the south face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 30" flared, galvanized iron pipe 22" into the ground. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 16" into the ground to refusal, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N54° E, 85.6 feet. I build a small mound of stones around this reference.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S66° 30' E, 98.2 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S63° W, 75.0 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N38° W, 95.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 22, 2004. Magnetic declination set in compass: 18° E.
NAD '83 UTM Zone 11 position: 5026561N, 327899E (plus or minus two meters).

RECEIVED BY
Morrow County Surveyor



Date: 1-4-14
Recd By: S.K.H.
No.: 2529 R15
Folder No.: _____

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: