

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 17
DIAGRAM



History of original corner establishment:

The original corner was established by George S. Pershin on September 14, 1871, under GLO contract No. 154, as follows:

Set a stone, 18" x 12" x 4", on top of hill for corner to sections 22, 23, 26 and 27.

Original corner evidence recovered:

Found the original corner stone lying loose on the east edge of a mound of stones. The original corner stone is 13" x 10" x 5" and is plainly marked with three notches on one (west) edge and two notches on another (south) edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 15" into the ground to bedrock. I bury the original corner stone along the north side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 18" iron rod set 15" into the ground with a 3/4" brass washer, marked "PLS 1636 23", attached at ground level, bears N21° E, 98.2 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 26", attached at ground level, bears S42° 30' E, 104.2 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 27", attached at ground level, bears S65° W, 87.9 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 22", attached at ground level, bears N63° W, 116.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 22, 2004. Magnetic declination set in compass: 15° E. NAD '83 UTM Zone 11 position: 5026525N, 328705E (plus or minus two meters).



RECEIVED BY
Morrow County Surveyor

Date: 1-04-14
Recd By: S.K.H.
No.: 2529 R17
Folder No.: _____

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on: