

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 15
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 16, 1871, under GLO contract No. 154, as follows:

Set a stone, 18" x 12" x 4", on west hillside for the 1/4 section corner to sections 27 and 34.

T2S R29E
1/4 S27
S34
PLS 1636
2004

Original corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 20" x 14" x 4" and is marked "1/4" on the south face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 16" into the ground. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 18" iron rod set 17" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N33° E, 78.3 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S42° E, 88.4 feet.
- A 5/8" x 18" iron rod set 17" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S9° 30' W, 67.6 feet.
- A 5/8" x 18" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N70° 30' W, 80.2 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 21, 2004. Magnetic declination set in compass: 17° E.
NAD '83 UTM Zone 11 position: 5024958N, 327820E (plus or minus two meters).



Dennis L. Gaylord

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY

Morrow County Surveyor

Date: 1-4-14
 Rec'd By: S.K.H.
 No.: 2529 V15
 Folder No.: _____