

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

X - 17  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin on September 14, 1871, under GLO contract No. 154, as follows:

Set a stone, 18" x 8" x 6", on northwest hillside for the 1/4 section corner to sections 34 and 35.

T2S R29E
1/4
S34 S35
PLS 1636
2004

**Original corner evidence recovered:**

Found the original corner stone solidly set in a mound of stones. The corner stone is 20" x 7" x 7" and is plainly marked "1/4" on the west face.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 26" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the northeast side of the pipe and build a mound of stones around the pipe, from which:

- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N68° E, 89.1 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S74° E, 85.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW, attached at ground level, bears S27° W, 103.5 feet.
- A 5/8" x 24" iron rod set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N53° W, 68.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 21, 2004. Magnetic declination set in compass: 17° E.  
NAD '83 UTM Zone 11 position: 5024107N, 328652E (plus or minus two meters).

  
*Dennis L. Gaylor*

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

**RECEIVED BY**  
Morrow County Surveyor

Date: 1-4-2014  
Rec'd By: S.K.H.  
No.: 2 S 2 9 X 1 7  
Folder No.: \_\_\_\_\_