

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

Z - 15  
DIAGRAM

T2S R29E
1/4 S34
S3
T3S
PLS 1636
2004

**History of original corner establishment:**

The original corner was established by George S. Pershin, Deputy, on September 6, 1871, under GLO contract No. 154, as follows:

Set a stone, 26" x 12" x 3", on east side of a hill for the 1/4 section corner to sections 34 and 3.

**Original corner evidence recovered:**

Found the original corner stone solidly set in a mound of stones, but tipped to the north. The corner stone is 26" x 16" x 5" and is plainly marked "1/4" on the south face.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 9" into the ground to bedrock. I place the corner stone along the east side of the pipe with the marked face down and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", wired to the rod at ground level, bears N36° E, 136.0 feet.
- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", wired to the rod at ground level, bears S39° 30' E, 118.8 feet.
- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", wired to the rod at ground level, bears S69° W, 102.6 feet.
- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", wired to the rod at ground level, bears N35° W, 95.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 7, 2004. Magnetic declination set in compass: 17° E.  
NAD '83 UTM Zone 11 position: 50233326N, 327819E (plus or minus two meters).



Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

**RECEIVED BY**

Morrow County Surveyor

Date: 1-04-14  
Recd By: S.K.H.  
No.: 2529715  
Folder No.: \_\_\_\_\_