

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, on September 6, 1871, under GLO contract No. 154, as follows:

Set a stone, 18" x 10" x 6", on east side of hill for corner to sections 34, 35, 2 and 3.

T2S R29E
S34 S35
S3 S2
T3S
PLS 1636
2004

Original corner evidence recovered:

Found the original corner stone solidly set on the north edge of a mound of stones. The original corner stone is 19" x 12" x 7" and is plainly marked with two notches on the east edge.

Monument and accessories established to perpetuate the original position of this corner:

In place of the corner stone, I set a 1" x 18" flared, galvanized iron pipe 14" into the ground to bedrock. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 35", attached at ground level, bears N19° E, 90.4 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears S27° 30' E, 120.8 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S3", attached at ground level, bears S58° W, 117.1 feet.
- A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 34", attached at ground level, bears N37° 30' W, 108.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on May 7, 2004. Magnetic declination set in compass: 15° 30' E.
NAD '83 UTM Zone 11 position: 5023308N, 328636E (plus or minus two meters).


Dennis R. Gaylord

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Morrow, State of Oregon, on:

RECEIVED BY

Morrow County Surveyor

Date: 1-4-14
Recd By: S.K.H.
No.: 2529217
Folder No.: _____