

OREGON CORNER RESTORATION FORM

Section 6 Township 3N Range 23E Index A-1

County ~~Morrow~~ Morrow Date 4/27/95

CORNER DESIGNATION \_\_\_\_\_ Condition Report Only

NW Corner  
 \_\_\_\_\_ Not Found  
 x Renewed  
 \_\_\_\_\_ Unrecorded  
 \_\_\_\_\_ Surveyed  
 \_\_\_\_\_ Reference

Previous Renewals/Surveys, etc. \_\_\_\_\_ Original survey by Thompson in 1867.  
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E"  
 1699812.

Monument(s) & Accessories Found: (Condition and Source)  
 Found 3" iron pipe with 3 1/2" standard GLO brass cap stamped as shown  
 below. Pipe surrounded by 3' stone mound.

Monument Detail \_\_\_\_\_ Sketch

T4N  
 R22E R23E  
S36	S31
 S1 | S6  
 T3N  
 1939

Monument Set (Procedures and Description)

New Accessories

Brass tag in power pole PPL 04-22, 369001 bears N35°00'W, 195.55'.  
 Brass tag in power pole PPL 03-22, 019901 bears S50°53'W, 121.33'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALS 13922 set in  
 center of abandoned road bears N33°37'E, 51.83'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALS 13922 set in  
 center of abandoned road bears S39°06'E, 50.29'.

Surveyor's Seal

Location & Comments  
 From Taggares Farm HQ  
 on Three Mile Canyon Road, Firm/Agency  
 go west 2.5 miles to a Haddock Surveying  
 a pumping station. Then go Address P. Box 1574  
 northwest 1.2 miles to a Pendleton, OR 97801  
 BPA substation. Then go Party Chief D. Haddock  
 north 1.0 mile to the Notes  
 corner. Witness S. Haddock

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*David L. Haddock*

OREGON  
 JULY 12, 1868  
 DAVID L. HADDOCK  
 952

RECEIVED BY  
 Morrow County Surveyor

Date 6/95  
 Initials DLH