

OREGON CORNER RESTORATION FORM

Section 6 Township 3N Range 23E Index E-1
 County Morrow ~~Humboldt~~ Date 4/27/95

CORNER DESIGNATION _____ Condition Report Only
 SW Corner Not Found
x Renewed
 _____ Unrecorded
 _____ Surveyed
 _____ Reference

Previous Renewals/Surveys, etc. _____ Original survey by Thompson in 1867.
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E"
 1699812. _____

Monument(s) & Accessories Found: (Condition and Source)
 Found 1" iron pipe with 2 1/2" standard GLO brass cap stamped as shown
 below.

Monument Detail	Sketch
T3N	
R22E R23E	
S1 S6	

S12 S7	
1939	

Monument Set (Procedures and Description)

New Accessories
 '5/8" rebar with plastic cap stamped PLS 529 CH2M Hill, bears S67°52'W,
 92.86'.

Brass tag on 2 1/2" steel pipe bears S16°26'E, 101.33'.
 Brass tag on 2 1/2" steel pipe at corner of chain link fence around
 substation bears N27°57'E, 86.24'.
 Brass tag on leg of steel transmission tower bears S79°25'E, 227.31'.

Location & Comments
 From Taggares Farm HQ
 on Three Mile Canyon Road,
 go west 2.5 miles to a
 a pumping station. Then go
 northwest 1.2 miles to a
 BPA substation. The corner
 lies near the southwest
 corner of the substation.

Compass Declination 20°
 Firm/Agency
 Haddock Surveying
 Address P. Box 1574
 Pendleton, OR 97801
 Party Chief D. Haddock
 Notes
 Witness S. Haddock

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

David L. Haddock

OREGON
 JULY 12, 1988
 DAVID L. HADDOCK
 652

RECEIVED BY

Morrow County Surveyor

Date 6/95

By DE