

OREGON CORNER RESTORATION FORM

Section 7 Township 3N Range 23E Index J-1

County Morrow Date 5/16/95

CORNER DESIGNATION \_\_\_\_\_ Condition Report Only

SW \_\_\_\_\_  
 \_\_\_\_\_ x Not Found  
 \_\_\_\_\_ Renewed  
 \_\_\_\_\_ Unrecorded  
 \_\_\_\_\_ Surveyed  
 \_\_\_\_\_ Reference

Previous Renewals/Surveys, etc. \_\_\_\_\_ Original survey by Thompson in 1867.  
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E"  
 1699812. \_\_\_\_\_

Monument(s) & Accessories Found: (Condition and Source)  
 Found 1" iron pipe with 2 1/2" standard GLO brass cap stamped as shown  
 below. Pipe is located at fence corner. \_\_\_\_\_

Monument Detail	Sketch
T3N R22E	Note: This corner is
S21 S22	erroneously marked.
S28 S27	It is at the correct
1939	location for the SW
	corner of Section 7.

Monument Set (Procedures and Description)

New Accessories

Attached brass washer stamped ORLS 852 and WALs 13922 to a 4" steel H  
 brace which bears N90°00'E, 259.10'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALs 13922  
 bears N87°21'W, 51.32', 3' south of steel fence post.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALs 13922  
 bears S1°02'W, 55.70', 2' east of steel fence post.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALs 13922  
 bears 1°23'E, 58.63'.  
 Location & Comments \_\_\_\_\_

Surveyor's Seal

From Taggares Farm HQ \_\_\_\_\_ Compass Declination 20°  
 on Three Mile Canyon Road, \_\_\_\_\_ Firm/Agency  
 go west 2.5 miles to a \_\_\_\_\_ Haddock Surveying  
 a pumping station. Then go \_\_\_\_\_ Address P. Box 1574  
 west along an old fence \_\_\_\_\_ Pendleton, OR 97801  
 line 0.6 mile to the \_\_\_\_\_ Party Chief D. Haddock  
 corner at a fence \_\_\_\_\_ Notes \_\_\_\_\_  
 junction. \_\_\_\_\_ Witness S. Haddock

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

DAVID L. HADDOCK  
 JULY 12, 1968  
 852

RECEIVED BY

Morrow County Surveyor

Date 6/95  
DE