

OREGON CORNER RESTORATION FORM

Section 10 Township 3N Range 23E Index J-13
 County Morrow ~~Wasatch~~ Date 5/16/95

CORNER DESIGNATION _____ Condition Report Only
 SW _____ Not Found
 _____ x Renewed
 _____ Unrecorded
 _____ Surveyed
 _____ Reference

Previous Renewals/Surveys, etc. _____ Original survey by Thompson in 1867.
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E"
 1699812. _____

Monument(s) & Accessories Found: (Condition and Source)
 Found 1" iron pipe with 2 1/2" standard GLO brass cap stamped as shown
 below. The monument is buried 21" below the surface in the road
 junction.

Monument Detail	Sketch
T3N R23E	
S9 S10	
S16 S15	
1939	

Monument Set (Procedures and Description)

New Accessories

Center of PPL pole 03-23, 169902 bears S53°13'E, 56.64' with brass
 washer stamped ORLS 852 AND WALIS 13922 nailed to face.
 Center of PPL pole 03-23, 169900 bears S46°07'W, 49.48' with brass
 washer stamped ORLS 852 AND WALIS 13922 nailed to face.
 Center of PPL pole 03-23, 099001 bears N8°05'E, 283.56' with brass
 washer stamped ORLS 852 AND WALIS 13922 nailed to face.
 Center of 16" Poplar bears N82°30'W, 132.78' with brass
 washer stamped ORLS 852 AND WALIS 13922 nailed to face.

Location & Comments
 From Taggares Farm HQ Compass Declination 20°
 on Three Mile Canyon Road, Firm/Agency
 go south 0.2 miles to the Haddock Surveying
 road junction. The corner Address P. Box 1574
 is located 21" below the Pendleton, OR 97801
 road surface in the party Chief D. Haddock
 junction. Notes _____
 Witness S. Haddock

Surveyor's Seal



RECEIVED BY
 Morrow County Surveyor

Date 6/95
 Surveyor DLE