

OREGON CORNER RESTORATION FORM

Section 7 Township 3N Range 23E Index J-3  
 County MORROW ~~WHEELER~~ Date 4/27/95

CORNER DESIGNATION South 1/4 Condition Report Only  
 Not Found  
 Renewed  
 Unrecorded  
 Surveyed  
 Reference

Previous Renewals/Surveys, etc. Original survey by Thompson in 1867. Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E" 1699812.

Monument(s) & Accessories Found: (Condition and Source)  
 Found 1" iron pipe with 2 1/2" standard GLO brass cap stamped as shown below.

Monument Detail	Sketch
<u>1/4</u>	<u>S7</u>
<u>S18</u>	
<u>1939</u>	

Monument Set (Procedures and Description)

New Accessories

Brass tag on 4" steel H brace bears N88°59'E, 143.93'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears N1°24'W, 45.72'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears N84°08'W, 44.77'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears S2°38'E, 43.69'.

Location & Comments  
 From Taggares Farm HQ  
 on Three Mile Canyon Road, Firm/Agency  
 go west 2.5 miles to a Haddock Surveying  
 a pumping station. Then go Address P. Box 1574  
 west 400' on an old fence Pendleton, OR 97801  
 line to the corner. Party Chief D. Haddock

Notes  
 Witness S. Haddock

Surveyor's Seal

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*David L Haddock*

OREGON  
 JULY 12, 1988  
 DAVID L. HADDOCK  
 852

RECEIVED BY

Morrow County Surveyor

Date 6/95  
DE