

OREGON CORNER RESTORATION FORM

Section 31 Township 3N Range 23E Index Z-1
 County ~~Morrow~~ Morrow Date 4/28/95

CORNER DESIGNATION SW
 Condition Report Only
 Not Found
 Renewed
 Unrecorded
 Surveyed
 Reference

Previous Renewals/Surveys, etc. _____ Original survey by Thompson in 1867.
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E"
 1699812. _____

Monument(s) & Accessories Found: (Condition and Source)
 Found 3" iron pipe with 3 1/2" standard GLO brass cap stamped as shown
 below. A large fence rock jack is at the corner.

Monument Detail	Sketch
T3N	
R22E R23E	
S36 S31	
----- -----	
S1 S6	
T2N	
1939	

Monument Set (Procedures and Description)

New Accessories
 Brass tag on leg of power line mile 10 tower 3 bears N13°11'E, 159.65',
 5/8" x 24" rebar with 2" A1 cap stamped ORLS 852 and WALLS 13922
 bears N87°24'W, 46.36' under fence.
 5/8" x 24" rebar with 2" A1 cap stamped ORLS 852 and WALLS 13922
 bears S0°40'W, 61.02' under fence.
 5/8" x 24" rebar with 2" A1 cap stamped ORLS 852 and WALLS 13922
 bears S86°27'E, 31.96' under fence.

Location & Comments
 From Taggares Farm HQ
 on Three Mile Canyon Road,
 go south 4.5 miles to the
 power line service road.
 Go west on this road to
 mile 10, tower 3.

Compass Declination 20°
 Firm/Agency _____
 Haddock Surveying _____
 Address P. Box 1574 _____
 Pendleton, OR 97801 _____
 Party Chief D. Haddock _____
 Notes _____
 Witness S. Haddock _____



RECEIVED BY
 Morrow County Surveyor

Date 6/95
 By DE