

OREGON CORNER RESTORATION FORM

Section 36 Township 3N Range 23E Index Z-21  
 County Morrow Date 5/16/95

CORNER DESIGNATION \_\_\_\_\_ Condition Report Only  
 SW \_\_\_\_\_ Not Found  
 \_\_\_\_\_ x Renewed  
 \_\_\_\_\_ Unrecorded  
 \_\_\_\_\_ Surveyed  
 \_\_\_\_\_ Reference

Previous Renewals/Surveys, etc. \_\_\_\_\_ Original survey by Thompson in 1867.  
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E"  
 1699812.

Monument(s) & Accessories Found: \_\_\_\_\_ (Condition and Source)  
 Found 1" iron pipe with 2 1/2" standard GLO brass cap stamped as shown  
 below.

Monument Detail	Sketch
T3N R23E	
S35 S36	
S2 S1	
T2N	
1939	

Monument Set (Procedures and Description)

**New Accessories**  
 Brass washer stamped ORLS 852 and WALs 13922 attached to the leg of  
 transmission tower mile 5, tower 4, bears S28°52'W, 162.44'.  
 5.8" rebar with 2" A1 cap stamped ORLS 852 and WALs 13922 bears  
 N0°00'E, 33.84'.  
 5.8" rebar with 2" A1 cap stamped ORLS 852 and WALs 13922 bears  
 N89°56'W, 51.93'.  
 5.8" rebar with 2" A1 cap stamped ORLS 852 and WALs 13922 bears  
 N88°25'E, 51.13'.

**Location & Comments**  
 From Taggares Farm HQ Compass Declination 20°  
 on Three Mile Canyon Road, Firm/Agency  
 go south 4.5 miles to the Haddock Surveying  
 powerline service road. Address P. Box 1574  
 Go east to tower mile 4, Pendleton, OR 97801  
 tower 4. Then go back west Party Chief D. Haddock  
 1.0 mile. Notes  
 Witness S. Haddock

Surveyor's Seal



*David L. Haddock*

RECEIVED BY

Morrow County Surveyor

Date 6/95  
 Made by DE  
 No. \_\_\_\_\_