

OREGON CORNER RESTORATION FORM

Section 36 Township 3N Range 23E Index Z-5  
 County Morrow Date 4/28/95

CORNER DESIGNATION \_\_\_\_\_  
 SE \_\_\_\_\_  
 Condition Report Only  
 Not Found \_\_\_\_\_  
 Renewed  \_\_\_\_\_  
 Unrecorded \_\_\_\_\_  
 Surveyed \_\_\_\_\_  
 Reference \_\_\_\_\_

Previous Renewals/Surveys, etc. \_\_\_\_\_ Original survey by Thompson in 1867.  
 Dependant resurvey by Gould in 1938 and 1939 under GLO letter "E" 1699812.

Monument(s) & Accessories Found: (Condition and Source)  
 Found 1" iron pipe with 2 1/2" standard GLO brass cap stamped as shown below. Sand had blown away from the corner leaving it standing vertical with 30" of it's length exposed.

Monument Detail	Sketch
T3N R23E	
S36   S35	
----- -----	
S6   S5	
T2N	
1939	

Monument Set (Procedures and Description)  
 Referenced monument. Removed monument and dug hole 30" deep. Set monument in original location hole with 4" of top exposed. Placed single 12" stone against monument.

New Accessories  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears N0°48'W, 24.81'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears S0°43'E, 43.44'.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears N87°21'W, 34.30' on south side of fence line.  
 5/8" x 24" rebar with 2" Al cap stamped ORLS 852 and WALIS 13922  
 bears S85°30'E, 50.11' on south side of fence line.  
 Location & Comments  
 From Taggares Farm HQ  
 on Three Mile Canyon Road, Firm/Agency  
 go south 4.5 miles to the Haddock Surveying  
 power line service road. Address P. Box 1574  
 Go east on this road to Pendleton, OR 97801  
 mile 10, tower 3, then party Chief D. Haddock  
 come back 1 mile. Notes \_\_\_\_\_  
 Witness S. Haddock

Surveyor's Seal  
 REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR  
 David L Haddock  
 OREGON  
 JULY 12, 1988  
 DAVID L. HADDOCK  
 852

RECEIVED BY

Morrow County Surveyor

Date 6/95

Initial by DE

No. \_\_\_\_\_