

# OREGON CORNER RESTORATION FORM

SECTION 5-6-7-8  
COUNTY: MORROW

TOWNSHIP 3 NORTH  
DATE: 03/01/2016

RANGE 26 EAST


CORNER DESIGNATION: E-5

PREVIOUS RENEWALS / SURVEYS, etc.

THE ORIGINAL CORNER SET BY U.S. DEPUTY SURVEYOR E.E.HAFT IN 1861. HE DROVE A CHARRED STAKE RAISED A MOUND WITH TRENCHES.  
OTIS GOULD CONDUCTED A DEPENDENT RESURVEY COMPLETED IN 1941. AT THAT TIME HE SET A 2" DIAMETER 3' LONG IRON POST WITH A BRASS CAP AND DUG PITS.  
IN THE EARLY 1970'S ROGERS SURVEYING INC. SURVEYED THIS CORNER AS PART OF WORK FOR DEVELOPMENT OF SABRE FARMS (SEE SURVEY 2016-1759C).

MONUMENT and ACCESSORIES FOUND: ( CONDITION AND SOURCE )  
NO EVIDENCE WAS FOUND OF THE MONUMENT.

DIAGRAM:



MONUMENT and ACCESSORIES SET ( PROCEDURES and DESCRIPTION )

SET A 2-1/2" BRASS CAP ON A 1" I.D. 30" LONG FLARED PIPE. MARKED AS SHOWN, AT POSITION PER 1973 SURVEY BY ROGERS SURVEYING FOR SABRE FARMS (2016-1759C), AS DETERMINED BY GRANT BOUNDARY METHOD AGAINST CORNERS EAST & WEST

REFERENCES SET:

- From a 3" diameter wood post the corner bears S6°38'W 8.7'
  - From a power pole (UEC 0799000) the corner bears N53°33'E 19.4'
  - From a tee fence post along the west edge of the canal the corner bears N46°31'W 25.2'
  - From a 4"X4" wood post the corner bears S73°08'W 10.9'
- (Bearings are Grid)

LOCATION and COMMENTS

NAD83 / 2011 Oregon North coordinates (International Feet)  
N 765515.52  
E 8431486.27

SURVEYORS SEAL

REGISTERED  
PROFESSIONAL LAND  
SURVEYOR

OREGON  
NOVEMBER 13, 2012  
DAVID P. BAALMAN  
86848PLS

RENEWS: 12/31/2017

RECEIVED BY:

MORROW COUNTY SURVEYOR  
DATE 5-17-2016  
REC'D BY: S.K.H.  
NO. 3N26E5

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.  
1455 COLUMBIA PARK TRAIL, #201  
RICHLAND, WA 99352  
(509) 783-4141

5-12-16