

OREGON CORNER RESTORATION FORM

SECTION 7 & 8
COUNTY: MORROW

TOWNSHIP 3 NORTH
DATE: 03/01/2016

RANGE 26 EAST


CORNER DESIGNATION: G-5

PREVIOUS RENEWALS / SURVEYS, etc.

THE ORIGINAL CORNER SET BY U.S. DEPUTY SURVEYOR E.E.HAFT IN 1861. HE DROVE A CHARRED STAKE RAISED A MOUND WITH TRENCHES. OTIS GOULD CONDUCTED A DEPENDENT RESURVEY COMPLETED IN 1941. AT THAT TIME HE FOUND A ROTTEN REMAINS OF AN OLD STAKE BEARING TRACES OF INCOMPLETE SCRIBE MARKS. HE SET A 2" DIAMETER 3' LONG IRON POST WITH A BRASS CAP AND DUG PITS.

MONUMENT and ACCESSORIES FOUND: (CONDITION AND SOURCE)
NO EVIDENCE WAS FOUND OF THE MONUMENT.

DIAGRAM:



MONUMENT and ACCESSORIES SET (PROCEDURES and DESCRIPTION)

SET A 2-1/2" BRASS CAP ON A 1" I.D. 30" LONG FLARED PIPE. MARKED AS SHOWN. POSITION BY MODIFIED SINGLE PROPORTION (SECTION 7-52 2009 BLM MANUAL) PER 1941 GLO DEPENDANT RESURVEY

REFERENCES SET:

From the southeast corner of a 6' chainlink fence at the overflow basin the corner bears S74°57'E 208.0'
From the Easterly leg of a steel communications tower the corner bears N69°26'E 231.9'
From a tee post on the south side of a farm road the corner bears N29°06'W 30.9'
From a tee post on the north side of a farm road the corner bears S45°W 1.3'
(Bearings are Grid)

LOCATION and COMMENTS

NAD83 / 2011 Oregon North coordinates (International Feet)
N 762891.99
E 8431589.70

The corner was set 1.5' below existing grade along the north side of an existing farm road.

RECEIVED BY:
MORROW COUNTY SURVEYOR
DATE 5-17-16
REC'D BY: S.K.H.
NO. 3N 26 G5

FIRM / AGENCY
ROGERS SURVEYING, Inc., P.S.
1455 COLUMBIA PARK TRAIL, #201
RICHLAND, WA 99352
(509) 783-4141

SURVEYORS SEAL

REGISTERED
PROFESSIONAL LAND
SURVEYOR

David P. Baalman
OREGON
NOVEMBER 13, 2012
DAVID P. BAALMAN
86848PLS

RENEWS: 12/31/2017

5-17-16