

OREGON CORNER RESTORATION FORM

COUNTY: Morrow. DATE: 03/28/17.

CORNER DESIGNATION: J-23, The North one-quarter corner of Section 13, Township 3 North, Range 26 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by E. E. Haft, under Contract No. 99 dated July 8, 1861. Notes state: The point for q. sec. corner Drove charred stake, raised a mound with trenches, as per instructions. Corner was recovered by Otis Gould, GLO Surveyor, in 1939. Gould's notes state: The 1/4 sec. cor., which is the remains of old stake, bearing traces of incomplete scribe marks. Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, with the marked stake deposited at the base, for 1/4 sec. cor., with brass cap, dug pits 18x18x12 ins., E. and W. of post, 3 ft. dist. This corner was recovered and tied by survey by Rogers Surveying in 1973, as shown on Survey No. 1759.

MONUMENT AND ACCESSORIES FOUND: No corner monument found. The corner monument has been destroyed by irrigation canal construction. I reestablish the position of this corner using the compass rule method between the recovered Northwest and reestablished Northeast corners of Section 13, using the Rogers Surveying Survey No. 1759 record.

MONUMENT MARKING DETAIL:

T3N R26E
1.5 FT
WC ----->
S12
1/4 -----
S13
2017
PLS 1106

MONUMENT SET: The corner point falls on a 18" diam. active irrigation pipe on the ground. At a point N 88°59'36" W, 1.50' from the corner point, set a 2 3/8" diameter brass cap on a 1 1/4"x30" galvanized iron pipe, 28" in the ground, marked as shown in "Monument Marking Detail".

New accessories:

A 5/8" by 24" rebar with red plastic cap bears N 55°56' E, 25.2'.

A 5/8" by 24" rebar with red plastic cap bears S 40°37' E, 52.4'.

A 5/8" by 24" rebar with red plastic cap bears S 43°52' W, 58.5'.

A 5/8" by 24" rebar with red plastic cap bears N 42°36' W, 18.9'.

The accessory rebars reference the witness corner monument. Accessory bearings are Oregon State Plane grid.

The red plastic caps are marked "ORPLS 1106 WAPLS 17372". All rebar accessories have "bearing object" signs wired to them. Wired a "Witness" sign to steel fence post set 2.5' North of the witness corner monument.

LOCATION AND COMMENTS: Witness Corner is located just South of the top of an irrigation canal berm on the South side of a concrete lined irrigation canal, and just west of an 18" active irrigation pipe.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(2011), epoch 2010.00:

1.50' Witness Corner: N = 760358.30
E = 8455266.05

True Corner: N = 760358.28
E = 8455267.55

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N26J23

RECEIVED BY
Morrow County Surveyor
Date: 4-11-2017
Rec'd By: S.K.H.
No.: 2017-17980C
Folder No.: 3N26J23

