

# OREGON CORNER RESTORATION FORM

COUNTY: Morrow. DATE: 03/28/17.

CORNER DESIGNATION: L-25, The East One-Quarter of Section 13, Township 3 North, Range 26 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by E. E. Haft, under Contract No. 93 dated September 11, 1860. Notes state: Set post q. sec. corner in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Corner was reestablished by proportionate measure by Otis Gould, GLO Surveyor, in 1939. Gould's notes state: Set an iron post, 3 ft. long, 1 in. Diam., 27 ins. in the ground for 1/4 sec. cor., with brass cap, dug pits 18x18x12 ins., N. and S. of post, 3 ft. dist. This corner was recovered and tied by survey by Rogers Surveying in 1973, as shown on Survey No. 1759.

MONUMENT AND ACCESSORIES FOUND: No corner monument found. The corner monument has been removed by farming and farm road building. I found a sheared off steel fence post below surface of farm road, N 45° E, 1.3' from corner point. At the corner point I found found 5, 5" nails, loose and flat, 6" below road surface. I reestablish the position of this corner using the compass rule method between the recovered Southwest corner of Section 18 and the recovered East one-quarter corner of Section 12, using the Rogers Surveying Survey No. 1759 record.

## MONUMENT MARKING DETAIL:

T3N  
R26E|R27E  
1/4  
S13|S18  
2017  
PLS 1106

MONUMENT SET: Set a 2" aluminum cap on 5/8" by 16" rebar with cap 8" below road surface, marked as shown in "Monument Marking Detail". Hit caliche rock and could not set brass cap monument.

New accessories:

A 5/8" by 24" rebar with red plastic cap bears N 29°03' E, 34.3'

A 5/8" by 24" rebar with red plastic cap bears S 70°14' W, 38.2'

A 5/8" by 24" rebar with red plastic cap bears S 01°56' W, 9.3'

A. 5/8" by 24" rebar with red plastic cap bears S 74°51' E, 38.6'

Accessory bearings are Oregon State Plane grid.

The red plastic caps are marked "ORPLS 1106 WAPLS 17372". All rebar accessories have "bearing object" signs wired to them. Wired a "Witness" sign to steel fence post set 9' South of corner monument.

LOCATION AND COMMENTS: Corner is located in an East-West private farm road, near the intersection of a farm road extending North.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(2011), epoch 2010.00:

N = 757764.03

E = 8457932.74

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

**RECEIVED BY**  
Morrow County Surveyor

\3N26L25 Date: 4-11-2017  
Rec'd By: S.K.H.  
No.: 2017-1798C  
Folder No.: 3N26L25

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-18*