

# OREGON CORNER RESTORATION FORM

SECTION 9 & 16  
COUNTY: MORROW

TOWNSHIP 3 NORTH  
DATE: 03/01/2016

RANGE 27 EAST

CORNER DESIGNATION: J-11


PREVIOUS RENEWALS / SURVEYS, etc.

THE ORIGINAL CORNER SET BY U.S. DEPUTY SURVEYOR E.E.HAFT IN 1861. HE SET A POST IN MOUND WITH TRENCH AND PITS AND DEPOSITED A PINT OF CHARCOAL. OTIS GOULD CONDUCTED A DEPENDENT RESURVEY COMPLETED IN 1941. AT THAT TIME HE SET A 2" DIAMETER 3' LONG IRON POST WITH A BRASS CAP AND DUG PITS. IN THE EARLY 1970'S ROGERS SURVEYING INC. SURVEYED THIS CORNER AS PART OF WORK FOR DEVELOPMENT OF SABRE FARMS (SEE SURVEY 2016-1759C).

MONUMENT and ACCESSORIES FOUND: ( CONDITION AND SOURCE )

THE 2.5" GLO BRASS CAP SET BY GOULD WAS FOUND. THE PIPE WAS BENT. IT WAS STRAIGHTENED AT THE POINT OF DISTURBANCE. THE RESTORED POSITION WAS CONFIRMED BY THE RECORD MEASUREMENTS FROM THE ROGERS 1970'S WORK.

DIAGRAM:



MONUMENT and ACCESSORIES SET ( PROCEDURES and DESCRIPTION )

FOUND GLO BRASS CAP (BENT), STRAIGHTENED AT POINT OF DISTURBANCE

REFERENCES SET:

From a tee post the corner bears S49°16'W 0.9'  
From a power pole the corner bears S88°05'E 50.5'  
From a tee post the corner bears N0°04'E 50.0'  
From a power pole the corner bears S89°51'W 262.5'  
(Bearings are Grid)

LOCATION and COMMENTS

NAD83 / 2011 Oregon North coordinates (International Feet)  
N 760692.38  
E 8471381.64

SURVEYORS SEAL

REGISTERED  
PROFESSIONAL LAND  
SURVEYOR

OREGON  
NOVEMBER 13, 2012  
DAVID P. BAALMAN  
86848PLS

RENEWS: 12/31/2017

5-17-16

RECEIVED BY:

MORROW COUNTY SURVEYOR

DATE 5-17-16

REC'D BY: S.K.H.

NO. 3N27J11

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.  
1455 COLUMBIA PARK TRAIL, #201  
RICHLAND, WA 99352  
(509) 783-4141