

**OREGON CORNER RESTORATION FORM**

COUNTY: Morrow. DATE: 04/18/18.

CORNER DESIGNATION: N-7, The South One-Quarter corner of Section 17, Township 3 North, Range 27 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by E. E. Haft, under Contract No. 93 dated September 11, 1860. Notes state: Set post for qtr. Sec corner in mound with trench and pits and deposited 1 pint of charcoal as per instructions. Corner was reestablished by proportionate measure by Otis Gould, GLO Surveyor, in 1940. Gould's notes state: Set an iron post, 3 ft. long, 1 in. Diam., 27 ins. in the ground, for 1/4 sec. cor., with marked brass cap, dug pits 18x18x12 ins., E. and W. of post, 3 ft. dist.

MONUMENT AND ACCESSORIES FOUND: Found Gould monument badly bent 6" below ground line. Set measure point, a hub and tack, at the straight, unbent portion of the Gould pipe monument and tied corner point.

**MONUMENT MARKING DETAIL:**

T3N R27E  
S17  
1/4 -----  
S20  
2018  
PLS 1106

MONUMENT SET: At the position of the found Gould monument, set a 2 3/8" diameter brass cap on a 1 1/4"x30" galvanized iron pipe, 27" in the ground in a 2 1/2' diameter earth mound. Monument is marked as shown in "Monument Marking Detail". Buried old bent monument below ground, North of new monument.

**New accessories:**

A 5/8" by 24" rebar with red plastic cap bears N 54°06' W, 67.5'.

A 5/8" by 24" rebar with red plastic cap bears N 12°09' W, 42.3'.

A 5/8" by 24" rebar with red plastic cap bears N 42°17' E, 58.4'.

A 5/8" by 24" rebar with red plastic cap bears N 62°39' E, 99.3'.

Bearings to rebar accessories are Oregon State Plane grid. The rebar accessories are set in a East-West fence line North of a farm road.

The red plastic caps are marked "ORPLS 1106 WAPLS 17372". All rebar accessories have "bearing object" signs wired to them. Wired a "Witness" sign to steel fence post set 2 1/2' East of the corner monument.

LOCATION AND COMMENTS: Corner is located 15' South of the center of a farm road running East-West.


OREGON STATE PLANE COORDINATE, North Zone, NAD 83(2011), epoch 2010:

N = 755270.86


E =8466195.92

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal



*William R. Wells*



*renews 6-30-18*

\3N27N-7

**RECEIVED BY**

Morrow County Surveyor

Date: 5-22-18

Rec'd By: S.K.H.

No.: 3N27N7

Folder No.: \_\_\_\_\_