

OREGON CORNER RESTORATION FORM

COUNTY: Morrow DATE: 01/15/14

CORNER DESIGNATION: T-21, T3S, R26E., The East One-Quarter Corner of Section 26.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by George Williams, Deputy Surveyor, under Contract No. 176 dated July 20, 1872. Notes state: "Set stone 24 x 7 x 6 for 1/4 sec cor." Notes also state the corner is 2.00 chains North of a dry gulch and road running from "Balm Fork" down to Sanford Canyon, East and West.

MONUMENT AND ACCESSORIES FOUND: Found 20 x 8 x 8" loose stone in fence jack marked "1/4". From this fence jack, fences extend East and South. There is a east-west gulch 2 chains South of corner point.

MONUMENT MARKING DETAIL:

T3S R26E
1/4
S26|S25
2014
PLS 1106

MONUMENT SET: I held the fence jack containing the loose original corner stone as best remaining evidence of the original corner location. At a point 0.5 feet North of the fence jack, set a 2 1/2" x 30" flared aluminum cap pipe 28" in the ground, marked as shown in "Monument Marking Detail".

New accessories set:

A 5/8" x 24" iron rebar with a 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 13° East, 49.7 feet. Accessory is 4' North of the NW corner of a cattle guard across the County Road.

A 5/8" x 24" iron rebar with a 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 87° East, 40.4 feet, in East-West fence line, beside wood fence post.

A 5/8" x 24" iron rebar with a 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 05° West, 27.4 feet. Set beside wood fence post in North-South fence line.

A 5/8" x 24" iron rebar with a 1 1/4" red plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 78° West, 37.7 feet. Set beside a wood fence post in the fence on the North side of the County Road..

Tops of all accessory rebars are 4" above ground level. Nailed a "Morrow County Witness" sign to rock jack just South of corner monument and placed large stone just North of monument.

LOCATION AND COMMENTS:

Corner monument is located at a fence jack with fences East and South, about 25' South of the centerline of the County Road.

This corner restoration form is filed in advance of a Land Partition for the Gwendolyn E. Thompson Estate. The recording number for this restoration is noted on said Land Partition Plat.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(2011)(Epoch 2010.00), International Feet:

N= 588834.76
E=8450518.81

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

\3S26MorrowT21

RECEIVED BY
Morrow County Surveyor
Date: 2-20-14
Rec'd By: S.K.H.
No.: 3S26T21
Folder No.: _____

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 06-30-14