

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: Z-1

The southwest corner of Section 31, T.3S., R.29E.,
W.M.
This corner was set by Williams under contract 176
in 1872.

1	DIAGRAM	1
1	T3S	1
1	R28E R29E	1
1	S36 S31	1
1	---	1
1	S1	1
1	T4S R28E	1
1	1996	1
1	PLS 852	1

His record states:
Set stone 22x8x10 for corner to Townships 3 and 4
South of Ranges 28 and 29 East - as per instructions.

Description of corner evidence found:
Found original stone with well chiseled notches on corners.

Description of monument and accessories I established to perpetuate the
original location of this corner:
At the position of the record stone, I set a 30" x 1.25" GIP with a
2.25" brass cap 20" in the ground stamped as shown in the diagram above.
I built a mound of stone around the monument.
I set 5/8" x 24" pins with red plastic cap stamped ORLS 0852 and WALS
13922 as bearing objects:
A pin bears S0°41'W, 46.18'.
A pin bears S88°51'W, 28.00'.
A pin bears N1°27'W, 40.31'.
A brass cap monumenting the northwest closing corner of Section 6 bears
N89°27'24"E, 177.59'.

This work was done October 21, 1996.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

**OREGON
JULY 12, 1968
DAVID L. HADDOCK
852**

Office of OREGON, I hereby certify that the within instrument was filed
in this office for record on the 18th day of NOVEMBER, 1996.
SKB by SKB
(COUNTY OFFICIAL) (DEPUTY)