

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: Z-3

South one quarter corner Section 31, T.3S., R.29E.,
W.M.
The original south township line was run in 1872 by
Williams under Contract 176.
His record states: Set a stone 18x13x6 from which;
a Pine 30" dia bears N50°W, 32 lks,
a Fir 10" dia bears S84°W, 42 lks.

1	DIAGRAM	1
1	T3S R29E	1
1	S31	1
1	---	1
1	4	1
1	T4S R29E	1
1	1996	1
1	PLS 852	1

Description of corner evidence found:
Found the record stone with clearly chiseled 1/4 in mound of stones.
A down and partially rotted Ponderosa Pine stump bears N50°W, 32 links,
with no visible scribing.

Description of monument and accessories I established to perpetuate the
original location of this corner:
At the position of the record stone, I set a 30" x 1.25" GIP with a
2.25" brass cap 26" in the ground stamped as shown in the diagram above.
I built a mound of stone around the monument.
Marked the following witness trees:
A 11" Western Larch bears S77°13'W, 70.00' scribed 1/4SBT.
A 18" White Fir bears S86°13'W, 11.43' scribed 1/4S31BT.
A 17" Ponderosa Pine bears N16°06"E, 25.59' scribed 1/4S31BT.
The brass cap for the north quarter corner of Section 6, Township 4
South, Range 29 East, W.M. bears N89°47'33"E, 154.24 feet.
The distances and bearings are measured to the head of a nail attaching
a brass washer stamped ORLS852 and WALSI3922 between the letters B and T
on each treee.

This work was done October 18, 1996.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

**OREGON
JULY 12, 1966
DAVID L. HADDOCK
852**

Office of _____ County of MORROW
State of OREGON, I hereby certify that the within instrument was filed
in this office for record on the 18th day of NOVEMBER, 1996.
SKB by _____
(COUNTY OFFICIAL) (DEPUTY)