

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index: Z-7

South one quarter corner Section 32, T.3S., R.29E., W.M.

The original south township line was run in 1872 by Williams under Contract 176.

His record states: Set a stone 18x10x4 from which;

a Pine 32" dia bears N26°W, 40 lks.

a Pine 26" dia bears S79°E, 1.22 lks.

1	DIAGRAM	1
1	T3S R29E	1
1	S32	1
1	---	1
1	4	1
1	T4S R29E	1
1	1996	1
1	PLS 852	1

Description of corner evidence found:

Found Ponderosa Pine stump within 20 feet of proportioned point. Stump had the very bottom part of a very old axe blaze showing with no scribing. The area where the corner and the other bearing tree would have been was located in an old logging skid road.

Description of monument and accessories I established to perpetuate the original location of this corner:

At record bearing and distance from the original bearing tree, I set a 30" x 1.25" GIP with a 2.25" brass cap 24" in the ground stamped as shown in the diagram above. I built a mound of stone around the monument.

Marked in the following witness trees:

A 21" Ponderosa Pine bears N82°44'E, 58.42' scribed 1/4S32BT.

A 21" Ponderosa Pine bears S9°26'W, 38.15' scribed 1/4SBT.

A 26" Ponderosa Pine bears S41°40"W, 21.72' scribed 1/4SBT.

A 16" Ponderosa Pine bears N21°26'W, 8.97' scribed 1/4S32BT.

The distances and bearings are measured to the head of a nail attaching a brass washer stamped ORLS852 and WALSI3922 between the letters B and T on each tree.

This work was done October 16, 1996.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

David L. Haddock

**OREGON
JULY 12, 1986
DAVID L. HADDOCK
852**

Office of OREGON, County of McRROW
 State of OREGON, I hereby certify that the within instrument was filed
 in this office for record on the 18th day of NOVEMBER, 1996.
DRS by SKB (DEPUTY)
 (COUNTY OFFICIAL)